Cosine is Nearly Human: The Reproducibility Ceiling of Perceptual Similarity

Benjamin TenWolde
Halıcıoğlu Data Science Institute
University of California, San Diego
betenwolde@ucsd.edu

Virginia R. de Sa
HDSI and Cognitive Science
University of California, San Diego
desa@ucsd.edu

Abstract

The NIGHTS dataset is widely used to test whether image-similarity metrics agree with human judgments of mid-level visual similarity. DreamSim, the model released with NIGHTS, reported large gains over DINO-based baselines, and those gains have been read as evidence that training on NIGHTS makes visual representations more human-aligned. We argue that the benchmark, as released, does not support that reading. Its evaluation set keeps only the triplets on which every voter agreed, about a fifth of a 100,000-triplet collection, and drops the many triplets where people split. We re-evaluate twelve perceptual-similarity models on the full released corpus. On its 64,420 non-tie triplets, cosine distance between frozen DINO features reaches 74.1% accuracy with no training at all. Nearly half of these triplets were judged by only three or four people, which limits what any accuracy number can show. If each triplet were voted on again by a new panel of the same size, the original majority would come back only about 89% of the time overall, and only 74–84% of the time on the split triplets the public release leaves out. Gains from training on NIGHTS therefore show that a model fits the votes that were collected, not that it would better match a new group of people; the problem lies in how the benchmark was built, not in ordinary overfitting. The labels also carry less than they appear to. Each vote compresses many visual differences into one choice, and the dataset's two human tasks, a forced choice between two candidates (2AFC) and a same-or-different judgment (JND), measure different things on the same images: JND voters judged both candidates different from the reference in 77% of the triplets carrying both labels, so a unanimous 2AFC choice means closer than the alternative, not similar. Fine-tuning also makes models more fragile under rotation, color, blur, and foreground/background changes; since no human judgments exist for these altered images, we report this as a property of the models, not a gap from humans. Plain cosine is not a universal answer either: on BAPPS, LPIPS beats every zero-shot DINO backbone on color, deblurring, and super-resolution distortions. NIGHTS supports a narrower claim than it has been used for: cosine distance on self-supervised features captures much of the reproducible signal in its current labels. Stronger claims about human alignment need a new benchmark with more votes per triplet, questions about one visual attribute at a time, per-rater data, and robustness tests.

1 Introduction

We make the claim that plain cosine distance on a self-supervised DINO-based backbone captures most of the human perceptual-similarity signal currently measurable in the image-triplet judgments from NIGHTS [Fu et al., 2023]. The competing claim is that supervised triplet training on NIGHTS (DreamSim and successors) yields strictly more human-aligned representations: DreamSim, a LoRA-

40th Conference on Neural Information Processing Systems (NeurIPS 2026). Track on Evaluations and Datasets.

fine-tuned DINO+CLIP+OpenCLIP ensemble trained on NIGHTS, reports 96.2% on the public 20,019-triplet release and subsequent work targets that number. We argue that the cosine baseline gives the narrower interpretation because NIGHTS, the benchmark that should adjudicate whether supervised triplet training improves human alignment, is itself filtered. The 20,019-triplet release is the unanimous-agreement subset of a 100,000-triplet collection; 35,580 ties (50/50 splits after aggregation) and roughly 44,000 weak-majority triplets (patterns such as 6-1, 5-1, 3-1, 2-1) are discarded. We note that human annotators disagreed on many triplets, and no further analysis or evaluation was published on these disagreements. Annotator-level data is also missing, and the benchmark's binary labels do not distinguish contested triplets from unanimous ones. We argue that the cosine baseline (such as provided with base DINO) is therefore not just a strong starting point, but it supplies most of the signal these labels can express. No stronger alignment claim trained against the same labels can be certified on them. The remaining gap is a labeling problem, and the successor benchmark required to move past it is what this paper motivates.

This is, to our knowledge, the first evaluation on the full NIGHTS corpus. We evaluate the 64,420 non-tie triplets by 5-fold cross-validation, training on 51,536 and testing on 12,884 per fold. We exclude all 35,580 ties from training and hold them out to audit bias: 35,569 are 1-1 and 11 are 2-2, since voting stopped at the first disagreement. NIGHTS provides only vote tallies, so we treat votes as anonymous ballots and resample each triplet's own votes to ask how often a fresh panel of the same size would reproduce its majority. This gives a reproducibility ceiling that accounts for the noise in the small per-triplet vote counts (47% of non-tie triplets have only 3 or 4 voters). We stratify test accuracy by vote pattern (X-0, X-1, X-2) and check left- versus right-candidate preference on tied votes.

Three findings support this claim. (i) Resampling the per-triplet votes gives a closed-form reproducibility ceiling for any 2AFC benchmark: on NIGHTS a fresh panel of the same size reproduces the observed majority about 89% of the time overall, and only 74–84% on the 2-1 and 3-1 triplets that make up 46% of the corpus. (ii) Cosine on the CLS embedding of a frozen DINOv1 backbone reaches 74% with no training. LoRA on NIGHTS-20k raises clean accuracy by 4–6 percentage points (pp) but increases foreground-only fragility from 2.0 to 7.7 pp. The tuned models rely on background cues humans do not need to recognize objects [Xiao et al., 2021]. (iii) The two NIGHTS labels, 2AFC ("which is more similar") and JND ("same or different"), are not interchangeable: JND voters judged the rejected candidate different from the reference in 94% of the 608 shared triplets, the chosen one in 82%, and both in 77%, so a unanimous 2AFC label means "closer than the alternative," not "similar," and neither label is a fixed ground truth. These results show that cognitive heads (Tversky, GCM, TNN) and fine-tuning do not beat plain cosine by more than the label noise can certify. Plain cosine on DINO-family backbones is the strongest zero-shot model. The appendix lists full per-fold numbers, additional ablations (harmonization, C-RADIOv4 distillation, Qwen3-VL-as-judge), BAPPS cross-benchmark sanity checks, paired significance tests, ImageNet/non-ImageNet splits, and qualitative triplet traces (Appendix J).

2 Related work

LPIPS [Zhang et al., 2018], generalizing pixel-domain SSIM [Wang et al., 2004], established deep-feature cosine distance as a perceptual metric. Subsequent work extended this with adversarially certified [Ghazanfari et al., 2024] and adversarially trained [Croce et al., 2025] variants. DreamSim [Fu et al., 2023] introduced synthetic Stable Diffusion v1.4 (SD) [Rombach et al., 2022] triplets and LoRA fine-tuning [Hu et al., 2022] for human alignment, reporting 96.2% on the filtered 20k and becoming the default backbone for follow-up work including DiffSim [Song et al., 2025] and the perceptual-alignment transfer analysis of Sundaram et al. [2024]. All of these evaluations use the same 20k filtered split as the original DreamSim paper.

Self-supervised backbones are the strongest perceptual base. Caron et al. [2021] showed that DINO's self-attention recovers object structure without supervision. Muttenthaler et al. [2022], Muttenthaler et al. [2023], and Conwell et al. [2024] found that SSL ViTs align with human similarity and brain responses above supervised CNNs, complementing earlier evidence that ImageNet [Deng et al., 2009] accuracy alone is a poor predictor of perceptual similarity [Kumar et al., 2022]. Oquab et al. [2024] scaled this to DINOv2 and DINOv3, and Chen et al. [2025] benchmarked 22 SSL backbones on mid-level vision tasks including NIGHTS. A second line of work injects human alignment at training time: AligNet [Muttenthaler et al., 2025] learns an affine transform into a THINGS-derived human

similarity space and distills it into vision backbones, and UniSim [Ghazanfari et al., 2025] trains a multi-task metric over 25 datasets including NIGHTS. A third line argues that attribute-similarity metrics (LPIPS, CLIP [Radford et al., 2021], DINO, DreamSim) miss *relational* similarity, the shared logic between visually different scenes, and proposes a VLM-based metric for this axis [Nguyen et al., 2026]. Across all of these approaches the final similarity operator is cosine distance (or a dot product on unit-norm embeddings), as is the case in retrieval and recommendation systems where cosine dominates despite its simplicity [Steck et al., 2024, You, 2025]. We do not propose a new alignment method. We audit what NIGHTS can and cannot tell us about any model's human alignment, and we show that cosine distance captures most of the reliable agreement in NIGHTS labels.

Cognitive theories of similarity provide alternative inductive biases. Tversky's [Tversky, 1977] contrast model uses asymmetric feature overlap in place of distance. Nosofsky's generalized context model adds selective dimensional attention [Nosofsky, 1986]. Gentner's structure-mapping theory aligns relational representations [Gentner, 1983]. Doumbouya et al. [2026] recently introduced a fully differentiable Tversky Neural Network. We evaluated these cognitive architectures directly against plain cosine-distance heads.

3 Method

3.1 Dataset reconstruction

The public NIGHTS release contains 20,019 triplets with binary vote columns. This is the unanimous subset of a larger 100,000-triplet collection that the authors released with raw vote proportions and per-triplet vote counts. The authors confirm that participant-level data was not retained, so we could not analyze individual variability across the 100,000 triplets. We converted the proportions to integer counts, computed the agreement pattern (larger-smaller, e.g., "6-1" for 6 left and 1 right), and partitioned the corpus into 64,420 non-tie triplets for training and evaluation and 35,580 tie triplets held out for the bias audit. DreamSim's trained and published results are on the 20k subset. This is the union of the X-0 (unanimous) patterns in the non-tie set. Its 20,019 triplets include one with a single vote and two with eleven; analyses that restrict the unanimous subset to 3–10 votes, or drop one of those extremes, report $N = 20{,}005$, $20{,}017$, or $20{,}018$. The vote-count distribution is skewed to small counts: 28.9% of non-tie triplets have 3 votes, 18.2% have 4, and 5.5% have at least 9.

3.2 Evaluation protocol

We use five-fold cross-validation with the commonly used seed 42 on the 64,420 non-tie triplets. Each fold has 12,884 test triplets and 51,536 training triplets. For LoRA, we hold out 10% of training for validation. We report mean and standard deviation of test accuracy across five folds by agreement pattern, and predictions on each fold's disjoint 7,116-triplet share of the 35,580 held-out ties.

Reproducibility ceiling. We estimate how often an independent panel of voters would reproduce a triplet's majority label by resampling its observed votes, assuming exchangeable voters (§6, vi). For each non-tie triplet with L left votes and R right votes ($V = L + R$), we draw V votes with replacement from the observed proportions and ask whether the new panel's majority matches the observed one; a tie in the new panel counts half. The binomial form gives this probability in closed form per (L, R) pattern. Averaging over 64,420 triplets gives the overall ceiling. This is an upper bound on accuracy these labels can certify: agreement beyond it may fit votes that would not recur. It does not bound accuracy against the fixed observed labels, which is trivially 100%.

3.3 Models evaluated

A model is a backbone, an adaptation (frozen, LoRA, retrained, or released weights), and a head that turns embeddings into a similarity; names follow the template `{Backbone}-{Adaptation}-{Head}-{Dataset}`. Table 5 (appendix) lists the factor values. Accuracies are on NIGHTS-100k unless stated otherwise. For zero-shot models we used cosine distance on the post-norm CLS token at 224×224 input. For LoRA models we applied rank-8 LoRA to the query, key, value, and output projections of every transformer block, unfroze the final LayerNorm, and trained with Schedule-Free AdamW [Defazio et al., 2024] (hyperparameters in Appendix E). The four head variants share the same LoRA budget: plain cosine distance, our

197k-parameter Cog head (frozen cosine alignment, GCM context, and Tversky contrast with learnable α, β), the inverse-frequency-stratified Cog, and the 197k-parameter Tversky Neural Network of Doumbouya et al. [2026] (product intersection and subtract-match difference functions, 256 features). DreamSim-Pretrained used the authors' public weights. DreamSim-Scratch retrained the full 3-model ensemble with rank-16 LoRA and margin-0.05 hinge loss for 6 epochs on each fold's training set using the published codebase unchanged, giving one checkpoint per fold.

4 Results

4.1 Main accuracies and the cost of unfiltering

Table 1 reports 5-fold mean accuracy on the full NIGHTS-100k for all primary models. Per-fold numbers are in Table 6 of the appendix. Figure 1 shows each model's accuracy on the unanimous-only X-0 subset (comparable to the published 20k) against its accuracy on the 100k corpus. We found that every model lost between 10.6 pp (LPIPS) and 17.2 pp (DreamSim-Pretrained) when evaluated on the full corpus vs the unanimous 20k published subset. On unanimous triplets the strongest models were near ceiling, while on weak-majority triplets they were near chance. NIGHTS-20k kept only the unanimous triplets, so the published scores were measured on the easy part of the data. Figure 1 shows the result as increasing disagreement is reincorporated.

Table 1: 5-fold CV accuracy for selecting the human-majority candidate on NIGHTS-100k non-tie ($N = 12{,}884$ per fold). †DreamSim-Pretrained uses released weights trained on the NIGHTS-20k training split; some of those triplets occur in our test folds, inflating its score. DreamSim-Scratch is retrained from scratch on NIGHTS-100k using the authors' published training recipe unchanged.

Model	Backbone + Head	Accuracy	Trainable params
LPIPS-AlexNet-Pretrained	AlexNet + linear probe	65.3 ± 0.2	0
DINOv1-ZS-CLS-cos	DINOv1 ViT-B/16	$\mathbf{74.1 \pm 0.5}$	0
DINOv2-ZS-CLS-cos	DINOv2 ViT-B/14	70.6 ± 0.4	0
DINOv3-ZS-CLS-cos	DINOv3 ViT-B/16	72.0 ± 0.4	0
DINOv1-LoRA-Cog	DINOv1 + Cog	75.1 ± 0.3	641,346
DINOv2-LoRA-Cog	DINOv2 + Cog	77.1 ± 0.5	641,346
DINOv2-LoRA-Cos	DINOv2 + Cosine	78.4 ± 0.4	443,904
DINOv2-LoRA-Cog-strat	DINOv2 + Cog + strat	76.3 ± 0.6	641,346
DINOv2-LoRA-TNN	DINOv2 + Doumbouya 2025 TNN	77.4 ± 0.5	640,515
DINOv3-LoRA-Cog	DINOv3 + Cog	$\mathbf{78.7 \pm 0.3}$	641,346
DreamSim-Pretrained†	DINO+CLIP+OpenCLIP, 20k weights	80.7 ± 0.2	$\sim$1.8M
DreamSim-Scratch	Retrained on NIGHTS-100k, votes$\geq$6	78.7 ± 0.7	$\sim$1.8M

4.2 Agreement-stratified reliability

Figure 2 plots accuracy against the vote-majority fraction for each model. The curves rise with agreement and share one shape: near ceiling on unanimous triplets, falling as disagreement grows, and close to chance on 2-1 triplets, where the human majority is a single vote. The spread between models widens with agreement: on 2-1 triplets the worst (LPIPS, 57.0%) and the best (DreamSim, 65.2%) differ by 8.2 pp, on 3-1 triplets the full spread is 13 pp, and on unanimous triplets it is about 20 pp. In other words, the more accurate models pull ahead only where human agreement is already strong; where people were split, all models sit near chance together. The extra accuracy comes from the triplets whose labels are reliable, not from doing better on the ones where people disagree.

4.3 A reproducibility ceiling from the vote counts

Table 2 reports the reproducibility ceiling for each subset: the probability that a fresh panel of the same size, drawn by resampling a triplet's observed votes with replacement, reproduces the observed majority label (a tie in the new panel counts half). The assumption is that each triplet's observed votes are exchangeable draws from one voter population (§6, vi). The ceiling is a property of the labels, not of any model. We report it as a ceiling on the accuracy these labels can certify, not a




Figure 1: The same models use 5-fold cross-validation on unanimous X-0 test folds (blue; disjoint from training, comparable to published 20k) and all non-tie NIGHTS-100k triplets (red). Each drops 10 to 17 points because test sets differ. Dashed line: DreamSim's published 96.2% on their 20k held-out split.




Figure 2: Accuracy versus human-agreement strength on NIGHTS-100k non-tie triplets. Accuracy rises with agreement for every model; DreamSim leads at most levels, but its released weights overlap our test folds. Unanimous patterns are pooled at 1.0; patterns with fewer than 100 triplets are omitted. Shaded band: the unanimous NIGHTS-20k subset.

bound on accuracy against the fixed observed labels: a deterministic model that memorized the observed majorities reaches 100%. The question is what a model generalizing from those labels can be expected to reproduce on a fresh vote. The overall ceiling on NIGHTS-100k non-tie is about 89%. The aggregate hides a split: 100% on unanimous triplets but far less where the majority hangs on one or two votes: a fresh panel of three agrees with a 2-1 majority only 74% of the time (20/27; N=18,454), a fresh panel of four with a 3-1 majority 84% (N=11,181), and a fresh panel of five with a 4-1 majority 94% (N=6,841). The 2-1 and 3-1 patterns together account for 46% of the non-tie corpus and drag the ceiling down.

No model reaches this ceiling: the best, DreamSim-Pretrained, scores 80.7% against the ≈89% the labels could certify, and on 2-1 triplets, where the label itself repeats only 74% of the time, every model sits below that bar (57.0–65.2%, Fig. 2). What the ceiling rules out is reading small gaps as better alignment: differences of a few percentage points fall inside the label noise, so they cannot be attributed to one model matching people better. The models that gained the most clean-image accuracy also lost invariance (§4.6), and 96.6% of DreamSim-Pretrained's disagreements with the majority label matched at least one dissenting voter.

The root cause is the NIGHTS collection procedure, which solicited votes until the first disagreement and then stopped. As a result, 47% of non-tie triplets were labeled by 3 or 4 voters. For a triplet with true preference $p = 0.6$, the probability that a 3-voter sample produces a majority in the other

Table 2: Reproducibility ceiling on NIGHTS-100k: the probability that a fresh panel of the same size, drawn by resampling each triplet's observed votes with replacement, reproduces the observed majority label. The strong-majority row spans its patterns (5-1 through 10-1); the overall value lies between 88.8% and 89.2% for any mix.

Subset	N	Repeatability
Unanimous (X-0)	20,018	100.0%
Strong majority (X-1, $X \geq 5$)	7,922	96.5–99.5%
Weak majority (4-1, 3-1, 2-1)	36,476	81.0%
All non-tie (NIGHTS-100k)	64,420	≈89%

direction is $\binom{3}{0}(0.6)^0(0.4)^3 + \binom{3}{1}(0.6)^1(0.4)^2 = 0.352$, so better than one in three observed majority labels would flip under re-annotation. A stable majority at $p = 0.6$ requires on the order of 35 votes per triplet. Model differences of a few percentage points on NIGHTS-100k fall within this label-noise band. They cannot be attributed to model quality without re-annotation data.

4.4 Cognitive priors and backbone ordering

We asked whether a psychologically motivated similarity head beats plain cosine. We tested three, Tversky asymmetric contrast, GCM selective attention, and the differentiable TNN of Doumbouya et al. [2026]. None did: cosine reached 78.4% ± 0.4 against 77.1% for Cog, 76.3% for inverse-frequency stratification, and 77.4% for TNN. The Tversky head shows why. It has two free weights, α for features only the reference has and β for features only the candidate has; unequal values would make similarity directional, but the fitted values came out nearly equal, so the head reduced to a symmetric measure and behaved like cosine. Retraining DreamSim from scratch on NIGHTS-100k with the authors' code gave $78.7 \pm 0.7\%$, 2.0 pp below its published weights on the same splits. Both gaps are smaller than the label noise: on 2-1 and 3-1 triplets a fresh panel would agree with the observed majority only 74–84% of the time, and differences under ∼10 pp are not separable from that noise (Section 4.3). A Cohen's-κ inter-model analysis is in Appendix C.

On NIGHTS-100k, zero-shot DINOv1 (74.1%) beat DINOv2 (70.6%) and DINOv3 (72.0%). Under LoRA the order reversed: DINOv3-LoRA-Cog 78.7%, DINOv2-LoRA-Cos 78.4%, DINOv1-LoRA-Cog 75.1%. Zero-shot rank does not predict fine-tuned rank (DINOv3 gained 6.7 pp).

Backbone family and scale. Cosine is not DINO-specific. We ran sixteen zero-shot backbones: eight CNNs (five supervised, three bio-inspired), two non-DINO ViTs (CLIP and supervised), and six DINO ViTs (DINOv1, DINOv3, and DINOv2 at S, B, L, and g). The ten non-DINO models span 65.3–72.4%, and six of them score above 70% (Table 12). Bigger is not better: DINOv2 falls monotonically over 52× in size on matched folds, and its two largest fall more than 5 pp behind DINOv1 cosine (Table 3), extending the CLIP/MAE trend of Fu et al. [2023]. Recent large models do worse: C-RADIOv4-SO400M at 58.2% after one fold-0 epoch and Qwen3-VL-4B at 63.0% (Appendix D).

Table 3: Zero-shot DINOv2 with cosine on NIGHTS-100k (5-fold mean ± s.d.). Accuracy falls monotonically with size. The 70.1% reference is the split-half agreement of the NIGHTS votes, the probability that the two halves of a triplet's votes choose the same majority; it is a conservative companion to the ≈89% fresh-panel ceiling of §4.3.

DINOv2	Params	NIGHTS-100k	vs. 70.1%	Unanimous X-0
ViT-S/14	21M	72.2 ± 0.5	$+2.1$	85.8
ViT-B/14	86M	70.6 ± 0.4	$+0.5$	83.9
ViT-L/14	300M	69.0 ± 0.2	-1.1	81.8
ViT-g/14	1.1B	68.4 ± 0.3	-1.7	80.5

The fine-tuning gain is real but not certifiable as alignment. The untrained DreamSim ensemble reached 74.5% versus 74.1% for frozen DINOv1 (0.4 pp from ensembling). Retraining reached 78.7% (4.2 pp from training), while the pretrained checkpoint gained 2.0 pp overall and 3.8 pp on its

overlapping 20k training subset. The 4.2 pp gain is not a color artifact: splitting by candidate color differences yields similar gains ($+3.9$ and $+4.9$ pp; Appendix D.7). Training learns real signal from the labels, but their 74–84% weak-majority reproducibility cannot establish better human agreement (§4.3).

4.5 The ceiling and the ranking on a second benchmark (BAPPS)

The same resampling applies to BAPPS [Zhang et al., 2018], which collects 5 votes per triplet ($N = 36{,}344$). A 3-2 majority is reproduced by a fresh panel of five only 68.3% of the time and a 4-1 majority 94.2%, so 2AFC benchmarks with few votes per triplet carry the same per-pattern limits on what their labels can certify.

On BAPPS, the ranking reverses: LPIPS beats every zero-shot DINO backbone by 1.4 to 5.6 pp, while DINO leads on NIGHTS by 5 to 10 pp. Only DreamSim-Pretrained (BAPPS 73.6, NIGHTS 80.7) and zero-shot DINOv1 (71.5, 74.1) are competitive on both (Table 4). Plain cosine is not competitive for low-level distortions; no single score captures performance across both benchmarks. Per-category comparisons appear in Appendix H.

Table 4: Zero-shot 2AFC accuracy on BAPPS validation (six distortion categories) and NIGHTS-100k. LPIPS leads on BAPPS, DINOv2/v3 on NIGHTS; only DreamSim-Pretrained and DINOv1 are competitive on both.

Model	BAPPS	NIGHTS-100k	Above 69.0 / 70.1%
LPIPS-AlexNet	72.9	65.3	
DINOv1-ZS	71.5	74.1	✓
DINOv2-ZS	67.3	70.6	
DINOv3-ZS	68.4	72.0	
DreamSim-Pretrained	73.6	80.7	✓

4.6 Shape, texture, and the axes of perceptual alignment

Accuracy against NIGHTS majority labels shows how often a model agrees, not which image features it uses. We therefore replicate the DreamSim appendix's stimulus-manipulation study [Fu et al., 2023], measuring accuracy under eleven manipulations.

Eleven stimulus manipulations. We apply each manipulation identically to all three images in a triplet from the unanimous 20k subset ($N = 2000$ sampled for speed), then score accuracy against the unchanged human label. The eleven manipulations cover four of the five DreamSim Figure 6 axes: orientation (90/180/270°), color (grayscale), shading (HSV V-channel histogram equalization), structure (Gaussian blur $\sigma \in \{1, 2, 4, 8\}$), and foreground/background (center disc of radius 0.35·image side or its complement). NIGHTS has no human labels for manipulated images, and we collected none. These tests measure model invariance, not human perceptual agreement; per-axis results are in Appendix D.5.

The same backbone, trained longer, loses invariance. Across 16 backbones, higher clean accuracy correlates with larger changes under manipulation, but this does not isolate training. We train DINOv2 with rank-8 LoRA on NIGHTS-20k for 8 epochs and test checkpoints {0,1,2,3,5,8} on the same 2000 triplets. Fragility is the mean absolute change in accuracy across the eleven manipulations, using absolute values because some increase accuracy. From epoch 0 to 1, clean accuracy rises from 84.6 to 89.8% and fragility from 1.9 to 5.1 pp. By epoch 8, accuracy falls to 85.2% while fragility climbs to 12.3 pp. With backbone and data fixed, training duration causes the invariance loss. The trajectory and attention overlays are in Appendix D.

Foreground-only fragility rises after LoRA. NIGHTS uses Stable Diffusion images with centered subjects and low-detail, nonuniform backgrounds. The foreground-only mask keeps a centered disc of radius 0.35 times the image side (about 38% of its area) and sets the surround to black. We apply the same mask to all three images without cropping or rescaling, preserving subject size and position. Removing the surround tests whether the model relies on its cues despite their low

detail. Zero-shot DINOv2 drops 2.0 pp; DINOv2 + LoRA drops 7.7 pp, a 3.8× increase. No human labels exist for these manipulated triplets, so this measures model invariance, not model–human divergence. In related natural-image categorization tasks, humans lose ∼3 pp under IN-9 background randomization [Xiao et al., 2021] and ∼1 pp on ObjectNet [Barbu et al., 2019]. The zero-shot drop is within that range; the LoRA drop is outside it, though these are not synthetic-triplet similarity judgments.

Fine-tuning makes models brittle; zero-shot DINO stays robust. LoRA-trained and DreamSim-Pretrained models are both more accurate on clean images and more fragile under the 11 manipulations than every zero-shot backbone. Each point of clean accuracy gained above the zero-shot band costs about a point of mean fragility (Appendix Figure 9), while zero-shot DINOv3 is the most invariant backbone tested. What DreamSim reports as better human alignment thus comes with more brittleness than the zero-shot ViT and DINO backbones.

A 2AFC lead does not carry over to JND. No model is trained for JND; all training uses the 2AFC labels alone. NIGHTS also ships a second human task, JND, on 608 of the 2AFC triplets: each candidate was shown briefly with the reference and judged "same" or "different," giving 1,216 reference–candidate pairs labeled by majority vote. We score the same frozen backbones on it, with no retraining: we reuse the embeddings from the main results and use the JND labels only to grade them, by how well the distance a backbone puts between a pair's two images separates the "different" pairs from the "same" ones (ROC AUC, which needs no cutoff). On the 2AFC triplets DINOv1 beats DINOv2 by 3.8 pp; on JND the lead disappears (AUC 0.674 vs. 0.677; Table 14). Across the fourteen zero-shot models, 2AFC accuracy barely predicts JND AUC (Spearman $\rho = 0.37$, $p = 0.19$). The two models trained on NIGHTS 2AFC score highest on both tasks (DreamSim 0.727, DINOv2+LoRA 0.720), though a single AUC carries a 95% interval of about ± 0.04. One benchmark number is thus a weak stand-in for perceptual alignment (Appendix G).

4.7 Model confidence versus the human vote split

Accuracy only shows whether a model picks the same image as most people. It does not ask whether the model hedges when people are also split on the choice. To check that, we turn each model's score into a probability of choosing the left image and read how confident it is (the calibration and tables are in Appendix D.4). No model is trained to output confidence; it is read off afterward with the same calibration for every model, so the differences come from the models, not the calibration. The human vote sets the target: a tie means no preference, a unanimous triplet full agreement.

The baseline is untrained cosine, and fine-tuning makes confidence worse, not better. On the 35,580 tied triplets, where the vote supports zero confidence, untrained DINOv1 cosine already reports 0.38 (LPIPS 0.25); fine-tuning raises this to 0.48 for DreamSim-Pretrained and to 0.80–0.95 for our own LoRA heads. Even on 2-1 triplets DreamSim-Pretrained sits at 0.49, and on weak-majority triplets, where the majority hangs on one or two votes, 11.8% of its predictions still exceed 0.9. On unanimous triplets the same upward shift helps, since the target is high (DreamSim 0.79 against untrained DINOv1's 0.58). So the overconfidence grows with training, measured against the untrained cosine it starts from.

Fine-tuning does have one edge, and we do not dispute it. A trained model's confidence rises and falls with the human vote more tightly than an untrained one: the two move together with rank correlation 0.76 for DreamSim-Pretrained, against 0.62 for zero-shot DINOv1 and 0.41 for LPIPS. So training teaches a model to follow how much people agree, without teaching it to be the right amount of unsure when they are split. Tables for each agreement level and the reliability curves are in Appendix D.4.

5 Discussion

Why cosine is nearly human, and why more training is not quite there. Plain cosine distance on the CLS embedding of a frozen DINO backbone reached 74% on NIGHTS-100k with no training, and its accuracy drop under the foreground-only mask stayed inside the range external human anchors suggest. LoRA fine-tuning raised clean accuracy from 84.6 to 89.3%, but that 4.7-pp gain came with a loss of invariance: the foreground-only drop grew from 2.0 to 7.7 pp while the object was

fully visible, and DreamSim-Pretrained was the most accurate and the most fragile model across orientation, color, heavy blur, and foreground and background masks (Fig. 7). With the same LoRA budget, no cognitive head (Tversky, GCM, TNN) beat plain cosine, and the Tversky heads learned no direction, so they reduced to symmetric measures. The 4.2-pp gain from training survives every control we ran. But NIGHTS cannot tell us whether the gain reflects better agreement with people in general or a closer fit to how these voters weighted features in these images. The labels are too noisy to decide: a fresh panel reproduces the majority only 81% of the time on weak-majority triplets and 74% on 2-1, so a 5-pp gap between models falls inside that noise. The JND conflict makes the same point without any resampling (Fig. 3). The 96.2% DreamSim reports is measured on the 20% of triplets where voters already agreed unanimously, where the ceiling is 100% by construction. Retraining the same ensemble on the full 100k drops it to 94.1% on that unanimous subset, 3.8 pp below the 97.9% it reaches when trained on the subset alone: the published weights are tuned to exactly the easy slice the 20k release keeps. We therefore read DreamSim not as a model that matches people better, but as one fit to the specific voters and images in the 20k set. To distinguish broader alignment from this kind of fit, we need labels that record which features each voter used and models that compare images feature by feature rather than reducing them to one distance.

NIGHTS is a single-axis benchmark presented as a general one. Perceptual similarity spans three levels: low-level pixel fidelity (where LPIPS and BAPPS operate), mid-level attributes of an object (pose, color, shape, texture, lighting), and high-level object identity and scene layout. NIGHTS sits between the mid and high levels: a voter combines several attributes and an overall judgment into one binary choice. We hypothesize that unanimous triplets differ mainly on one mid-level feature, while trade-offs across features drive the weak-majority votes in the 80,000 triplets NIGHTS-20k excluded. The 16-pp gap between DreamSim's 96.2% on 20k and 80.7% on 100k is the cost of leaving that single-axis subset. The reproducibility ceiling reflects more than random noise. Voters may weigh features of the same images differently, but the 20k release hides these disagreements by keeping only unanimous triplets. A model tuned to one benchmark inherits that benchmark's particular set of voters, so scoring well on it is not the same as matching people in general.

Voting is preference, not an explanation. Both NIGHTS 2AFC ("which is more similar?") and NIGHTS-JND ("same or different?") collect a single bit per voter. Multi-axis differences (shape, color, pose, lighting, composition, background, identity) collapse into one vote that records the choice but not the attribute the voter used. The two labels can be compared directly. NIGHTS-JND reuses 608 unanimous 2AFC triplets, so each of their 1,216 reference–candidate pairs carries a 2AFC label (its candidate won or lost) and a JND label ("same" or "different" from the reference). JND majorities judged 94% of rejected candidates and 82% of chosen candidates different from the reference, a pattern consistent with the 2AFC preference (Figure 3). The difference varies with the number of 2AFC votes; both rates round to 91% in the 10–0 group, which contains only 22 triplets. In 77% of triplets, JND majorities judged both candidates different. Among the 137 triplets in which exactly one candidate was judged "same," it was the rejected candidate in 34 (25%), and the chosen candidate in 103 (75%). Both tasks also split internally: 47% of JND pairs and 69% of non-tie 2AFC triplets have a dissenting voter (Appendix K). A 2AFC vote is a forced comparison with no "neither" option, so a candidate can win unanimously by being the less different of two clearly different images. A unanimous 2AFC label thus means "closer than the alternative," not "similar to the reference." Whether a shared background should count toward similarity is itself one of these collapsed axes: the fragility results in §4.6 show that tuned models weigh it more heavily than untuned ones, but without per-rater attribute labels we cannot tell whether human voters weighed it at all. The tasks were applied to the same image pairs, so their disagreement cannot be attributed to differences in the images. Treating either label as ground truth privileges one meaning of "similar." Without per-voter labels, we cannot tell whether people perceived the images differently or interpreted the questions differently. The same release omits annotator identifiers and demographics.

5.1 A protocol for the next benchmark

Models are not the bottleneck; the labels are. Today's vision backbones already do the things perceptual similarity needs: they match points on an object as its pose changes [Amir et al., 2022, Caron et al., 2021], stay stable when the view rotates [Naseer et al., 2021, Raghu et al., 2021], can be tuned to judge by shape rather than texture [Geirhos et al., 2019, Hermann et al., 2020], and their sensitivity to color, rotation, and blur can each be measured (Appendix I). What they cannot get past



Figure 3: The two human labels on the same image pairs. Left: share of candidates JND voters judged "different" from the reference, by the triplet's 2AFC vote count: 94% of rejected and 82% of chosen candidates overall, with a gap that does not grow with 2AFC consensus. In 77% of triplets both candidates are judged different, so a unanimous 2AFC choice certifies "closer," not "similar." Right: one of the 34 triplets (of the 137 where JND finds exactly one candidate identical) in which that candidate is the one 2AFC rejected. Full breakdown in Appendix K.

is a label that records only one forced choice per triplet and discards which feature the person used to make it. A benchmark that fixed this would let us ask whether a model is right for the right reason. It would: **(1)** change one feature at a time, by taking a single image and editing it by a small and a large amount along one dimension such as brightness or blur, so the correct answer is fixed without asking anyone; **(2)** ask the same question NIGHTS asked ("which image is more like the center one?") without naming the dimension, and after the choice have the person mark on the image what looked different, say where, and rate how sure they were, so each vote comes with its reason; **(3)** release every person's own responses, not just the vote totals, so a model's mistakes can be checked against how people actually split; **(4)** collect enough votes per triplet to push the reproducibility ceiling of §4.3 close to 100%, so a reported gap between models means something; **(5)** fix the train/test splits and tie rules and ship them with the data, so every model is scored the same way; and **(6)** report accuracy on held-out image distortions next to the headline number, so robustness is visible.

A first study re-annotates 3,000 NIGHTS triplets stratified by agreement pattern, with 30 annotators per triplet, no early stopping, and per-rater votes in the release. A second condition has the same annotators judge the §4.6 manipulations of those triplets, supplying the human baseline the invariance results currently lack, and the 608 triplets shared with NIGHTS-JND, so the 2AFC–JND dissociation can be traced to raters. Simply re-annotating the same images would not help: more votes would only shrink the error bars, not answer the finer questions a multi-axis test is built to ask.

6 Limitations

Scope caveats. **(i)** The model accuracies in Table 1 are specific to NIGHTS, although the reproducibility ceiling itself transfers to other 2AFC benchmarks (§4.5). **(ii)** We ran sixteen backbones zero-shot but fine-tuned only the three DINO models, and the size sweep covers one family (DINOv2, S to g); other families may scale differently. **(iii)** All LoRA models used rank 8 so that the heads were compared at equal adapter capacity; we did not sweep the rank. **(iv)** When DreamSim-Pretrained disagreed with the majority label, a minority voter had made the same choice in 96.6% of cases; without per-voter labels we cannot tell whether those triplets were ambiguous or whether the model shares a bias with those voters. **(v)** The claim that some JND/2AFC disagreements reflect different readings of the instructions rests on one co-author looking at ten JND pairs, not a systematic re-annotation, so we treat it only as a hypothesis. **(vi)** The reproducibility ceiling resamples each triplet's observed votes assuming exchangeability, taking the observed vote fraction at face value, which is optimistic for small panels; different pools, instructions, and within-session effects would lower real agreement. Independent re-annotation reproducing the labels well above it would overturn our reading. **(vii)** Public NIGHTS votes lack rater IDs, demographics, per-rater consistency, and quality filters, so rater bias, subgroup accuracy, and majorities within a representative subpopulation cannot be tested [Henrich et al., 2010].

Broader impact and reproducibility

We also release the seed-42 5-fold definitions, as well as per-triplet test predictions for all models. We release the retrained checkpoints, the standalone reproducibility-ceiling script parameterized by vote count, and the analysis notebooks that regenerate every table and figure from the released predictions, at `https://github.com/benlten/cosine_is_nearly_human` under the MIT license. All human judgment data were obtained from the public NIGHTS, NIGHTS-JND, and BAPPS releases. There was no collection of new human data.

Acknowledgements and disclosures

Funding. Benjamin TenWolde is supported by the Department of Defense (DoD) SMART Scholarship-for-Service Program. This work used hardware originally provided by funding from Sony and NSF IIS-CRCNS-2208362.

Competing interests. The authors declare no competing interests.

References

Shir Amir, Yossi Gandelsman, Shai Bagon, and Tali Dekel. Deep ViT features as dense visual descriptors. *ECCV Workshops*, 2022. What is Motion For? workshop; arXiv:2112.05814.

Andrei Barbu, David Mayo, Julian Alverio, William Luo, Christopher Wang, Dan Gutfreund, Josh Tenenbaum, and Boris Katz. ObjectNet: A large-scale bias-controlled dataset for pushing the limits of object recognition models. In *NeurIPS*, 2019.

Mathilde Caron, Hugo Touvron, Ishan Misra, Hervé Jégou, Julien Mairal, Piotr Bojanowski, and Armand Joulin. Emerging properties in self-supervised vision transformers. In *ICCV*, 2021.

Xuweiyi Chen, Markus Marks, and Zezhou Cheng. Probing the mid-level vision capabilities of self-supervised learning. In *CVPR*, 2025.

Colin Conwell, Jacob S. Prince, Kendrick N. Kay, George A. Alvarez, and Talia Konkle. A large-scale examination of inductive biases shaping high-level visual representation in brains and machines. *Nature Communications*, 15(1):9383, 2024.

Francesco Croce, Christian Schlarmann, Naman Deep Singh, and Matthias Hein. Adversarially robust CLIP models can induce better (robust) perceptual metrics. *SaTML*, 2025. arXiv:2502.11725.

Aaron Defazio, Xingyu (Alice) Yang, Harsh Mehta, Konstantin Mishchenko, Ahmed Khaled, and Ashok Cutkosky. The road less scheduled. *NeurIPS*, 37:9974–10007, 2024.

Jia Deng, Wei Dong, Richard Socher, Li-Jia Li, Kai Li, and Li Fei-Fei. ImageNet: A large-scale hierarchical image database. In *CVPR*, 2009.

Moussa Koulako Bala Doumbouya, Dan Jurafsky, and Christopher D. Manning. Tversky neural networks: Psychologically plausible deep learning with differentiable Tversky similarity. *ICLR*, 2026. arXiv:2506.11035.

Thomas Fel, Ivan F. Rodriguez Rodriguez, Drew Linsley, and Thomas Serre. Harmonizing the object recognition strategies of deep neural networks with humans. In *NeurIPS*, 2022.

Stephanie Fu, Netanel Y. Tamir, Shobhita Sundaram, Lucy Chai, Richard Zhang, Tali Dekel, and Phillip Isola. DreamSim: Learning new dimensions of human visual similarity using synthetic data. In *NeurIPS*, 2023.

Robert Geirhos, Patricia Rubisch, Claudio Michaelis, Matthias Bethge, Felix A. Wichmann, and Wieland Brendel. ImageNet-trained CNNs are biased towards texture; increasing shape bias improves accuracy and robustness. In *ICLR*, 2019.

Dedre Gentner. Structure-mapping: A theoretical framework for analogy. *Cognitive Science*, 7(2): 155–170, 1983.

Sara Ghazanfari, Alexandre Araujo, Prashanth Krishnamurthy, Farshad Khorrami, and Siddharth Garg. LipSim: A provably robust perceptual similarity metric. *ICLR*, 2024. arXiv:2310.18274.

Sara Ghazanfari, Siddharth Garg, Nicolas Flammarion, Prashanth Krishnamurthy, Farshad Khorrami, and Francesco Croce. Towards unified benchmark and models for multi-modal perceptual metrics. In *CVPR Workshops*, 2025.

Joseph Henrich, Steven J. Heine, and Ara Norenzayan. The weirdest people in the world? *Behavioral and Brain Sciences*, 33(2–3):61–83, 2010.

Katherine L. Hermann, Ting Chen, and Simon Kornblith. The origins and prevalence of texture bias in convolutional neural networks. In *NeurIPS*, 2020.

Edward J. Hu, Yelong Shen, Phillip Wallis, Zeyuan Allen-Zhu, Yuanzhi Li, Shean Wang, Lu Wang, and Weizhu Chen. LoRA: Low-rank adaptation of large language models. In *ICLR*, 2022.

Manoj Kumar, Neil Houlsby, Nal Kalchbrenner, and Ekin D. Cubuk. Do better ImageNet classifiers assess perceptual similarity better? *TMLR*, 2022.

Drew Linsley, Dan Shiebler, Sven Eberhardt, and Thomas Serre. Learning what and where to attend. In *ICLR*, 2019.

Lukas Muttenthaler, Charles Y. Zheng, Patrick McClure, Robert A. Vandermeulen, Martin N. Hebart, and Francisco Pereira. VICE: Variational interpretable concept embeddings. In *NeurIPS*, 2022.

Lukas Muttenthaler, Jonas Dippel, Lorenz Linhardt, Robert A. Vandermeulen, and Simon Kornblith. Human alignment of neural network representations. In *ICLR*, 2023.

Lukas Muttenthaler, Klaus Greff, Frieda Born, Bernhard Spitzer, Simon Kornblith, Michael C. Mozer, Klaus-Robert Müller, Thomas Unterthiner, and Andrew K. Lampinen. Aligning machine and human visual representations across abstraction levels. *Nature*, 647:349–355, 2025.

Muhammad Muzammal Naseer, Kanchana Ranasinghe, Salman H. Khan, Munawar Hayat, Fahad Shahbaz Khan, and Ming-Hsuan Yang. Intriguing properties of vision transformers. *NeurIPS*, 34: 23296–23308, 2021.

Thao Nguyen, Sicheng Mo, Krishna Kumar Singh, Yilin Wang, Jing Shi, Nicholas Kolkin, Eli Shechtman, Yong Jae Lee, and Yuheng Li. Relational visual similarity. *CVPR*, 2026. arXiv:2512.07833.

Robert M. Nosofsky. Attention, similarity, and the identification-categorization relationship. *Journal of Experimental Psychology: General*, 115(1):39–57, 1986.

Maxime Oquab, Timothée Darcet, Théo Moutakanni, Huy V. Vo, Marc Szafraniec, Vasil Khalidov, Pierre Fernandez, Daniel Haziza, Francisco Massa, Alaaeldin El-Nouby, Mahmoud Assran, Nicolas Ballas, Wojciech Galuba, Russell Howes, Po-Yao Huang, Shang-Wen Li, Ishan Misra, Michael Rabbat, Vasu Sharma, Gabriel Synnaeve, Hu Xu, Hervé Jégou, Julien Mairal, Patrick Labatut, Armand Joulin, and Piotr Bojanowski. DINOv2: Learning robust visual features without supervision. *TMLR*, 2024. arXiv:2304.07193.

Alec Radford, Jong Wook Kim, Chris Hallacy, Aditya Ramesh, Gabriel Goh, Sandhini Agarwal, Girish Sastry, Amanda Askell, Pamela Mishkin, Jack Clark, Gretchen Krueger, and Ilya Sutskever. Learning transferable visual models from natural language supervision. In *ICML*, 2021.

Maithra Raghu, Thomas Unterthiner, Simon Kornblith, Chiyuan Zhang, and Alexey Dosovitskiy. Do vision transformers see like convolutional neural networks? *NeurIPS*, 34:12116–12128, 2021.

Robin Rombach, Andreas Blattmann, Dominik Lorenz, Patrick Esser, and Björn Ommer. High-resolution image synthesis with latent diffusion models. In *CVPR*, 2022.

Yiren Song, Xiaokang Liu, and Mike Zheng Shou. DiffSim: Taming diffusion models for evaluating visual similarity. In *ICCV*, 2025.

Harald Steck, Chaitanya Ekanadham, and Nathan Kallus. Is Cosine-Similarity of embeddings really about similarity? In *WWW Companion*, 2024.

Shobhita Sundaram, Stephanie Fu, Lukas Muttenthaler, Netanel Y. Tamir, Lucy Chai, Simon Kornblith, Trevor Darrell, and Phillip Isola. When does perceptual alignment benefit vision representations? In *NeurIPS*, 2024.

Amos Tversky. Features of similarity. *Psychological Review*, 84(4):327–352, 1977.

Zhou Wang, Alan C. Bovik, Hamid R. Sheikh, and Eero P. Simoncelli. Image quality assessment: From error visibility to structural similarity. *IEEE TIP*, 13(4):600–612, 2004.

Kai Yuanqing Xiao, Logan Engstrom, Andrew Ilyas, and Aleksander Mądry. Noise or signal: The role of image backgrounds in object recognition. In *ICLR*, 2021.

Kisung You. Semantics at an angle: When cosine similarity works until it doesn't. *arXiv preprint arXiv:2504.16318*, 2025.

Richard Zhang, Phillip Isola, Alexei A. Efros, Eli Shechtman, and Oliver Wang. The unreasonable effectiveness of deep features as a perceptual metric. In *CVPR*, 2018.

A Model naming and factor values

Throughout the paper we identify each evaluated model by a four-part name of the form `{Backbone}-{Adaptation}-{Head}-{Dataset}`. Table 5 enumerates the possible values each component can take. Backbones are the feature extractors. Adaptation describes whether the backbone is frozen, partially trained via LoRA adapters, fully retrained, or used with externally-supplied pretrained weights. The head is the module that converts two (or three) backbone outputs into a similarity score; nine variants are compared including plain cosine distance, three cognitive-science-motivated architectures (Cog-v1 through Cog), the published Tversky Neural Network of Doumbouya et al. [2026], the DreamSim margin-hinge ensemble loss, and a VLM logit-ratio judge. Dataset values record which NIGHTS subset a model was trained and evaluated on; omitting the dataset suffix defaults to NIGHTS-100k, our primary evaluation target.

Table 5: Model naming scheme. Every model name in the paper is a concatenation of one value from each of the four rows. Example: `DINOv3-LoRA-Cog` uses DINOv3 as backbone, rank-8 LoRA on qkv/proj, our Cog head (frozen cosine alignment + GCM context + Tversky contrast), evaluated on the full NIGHTS-100k corpus.

Component	Values	Description
Backbone	DINOv1, DINOv2, DINOv3	Self-supervised ViTs
	C-RADIOv4	Distillation of DINOv3+SigLIP2+SAM3
	Qwen3-VL-4B	Vision-language model
	DreamSim	DINO+CLIP+OpenCLIP ensemble
	AlexNet-lin	LPIPS classical backbone
Adaptation	ZS	Zero-shot, frozen backbone
	LoRA	Rank-8 LoRA on qkv/proj + head trained
	Pretrained	External weights (trained on NIGHTS-20k)
	Scratch	Retrained on the stated dataset from scratch
Head	CLS-cos	Cosine distance on CLS token
	Tversky-frozen	Tversky contrast, $\alpha = \beta = 0.5$
	Cog-v1	Learned cross-attention + context + Tversky
	Cog-v2	Shared alignment + bottleneck + Tversky
	Cog	Frozen cosine align + GCM context + Tversky
	Cog-strat	Cog with inverse-frequency sampling
	TNN	Doumbouya 2025 differentiable TNN
	Hinge-ens	Margin hinge loss over ensemble features
	VLM-judge	Qwen3-VL logit ratio on A/B choice
Dataset	NIGHTS-100k	Full 100k, 64,420 non-tie, 35,580 ties held out
	NIGHTS-100k-unan	X-0 subset, N=20,017
	NIGHTS-100k-weak	2-1/3-1/4-1 subset, N=36,476
	NIGHTS-20k (published)	Filtered unanimous release

B Per-fold raw numbers

Table 1 reports mean accuracy and standard deviation over five cross-validation folds. Table 6 gives the accuracy of each of the twelve models on each fold. We form folds from the 64,420 non-tie triplets using fixed seed 42 and reuse the same indices for every model, so comparisons are not affected by data shuffling. For trained models, no fold differs from its model's mean by more than 1 percentage point, and the model rankings stay the same on every fold.

Table 6: Per-fold accuracies (%) on the NIGHTS-100k non-tie corpus (N=64,420 triplets; 12,884 per test fold; 5-fold cross-validation, seed 42). Each row is one model identified by the naming scheme of Table 5. Columns are the five test folds; the same fold definitions are reused across all models. Mean and standard deviation over the five folds are reported in Table 1 of the main body.

Model	Fold 1	Fold 2	Fold 3	Fold 4	Fold 5
LPIPS-AlexNet-Pretrained	65.4	65.5	65.3	65.3	65.0
DINOv1-ZS-CLS-cos	74.8	74.0	73.8	73.6	74.2
DINOv2-ZS-CLS-cos	70.8	71.0	70.8	70.3	70.0
DINOv3-ZS-CLS-cos	72.4	72.3	72.1	71.4	71.7
DINOv1-LoRA-Cog	74.8	75.6	75.0	75.3	74.9
DINOv2-LoRA-Cog	77.4	77.5	76.2	77.4	77.1
DINOv2-LoRA-Cos	78.7	78.4	77.6	78.3	78.8
DINOv2-LoRA-Cog-strat	76.4	76.4	76.2	75.8	77.2
DINOv2-LoRA-TNN	77.2	77.5	76.7	77.4	78.1
DINOv3-LoRA-Cog	78.7	78.9	78.3	78.4	79.1
DreamSim-Pretrained	80.5	80.9	80.4	80.9	80.8
DreamSim-Scratch	79.4	79.7	77.9	78.4	78.2

C Full Cohen's κ matrix

Cohen's κ quantifies the agreement between two classifiers after correcting for the agreement expected by chance. We compute κ pairwise between eleven of the twelve models in Table 1 (the TNN head is omitted) on the pooled 64,420 non-tie test predictions (every triplet appears in exactly one fold's test split, so the pooled set is a disjoint union of the five held-out folds). Values near 1 indicate redundant models that would gain little from ensembling; values near 0.4–0.6 indicate models that make different errors and are candidates for ensembling. In Figure 4 the three DINO zero-shot entries cluster tightly ($\kappa > 0.63$), as do the five LoRA-adapted DINO variants ($\kappa > 0.6$), confirming that the DINO family makes highly correlated errors. LPIPS sits further out ($\kappa = 0.25$–0.36 with any DINO-family model), which is consistent with its different underlying feature basis. DreamSim-Pretrained and DreamSim-Scratch reach $\kappa = 0.75$, the highest pairwise agreement in the matrix: retraining the DreamSim ensemble on NIGHTS-100k does not shift its error structure, it only shifts the overall accuracy by 2 pp. The scratch model is structurally the same predictor, trained on a cleaner subset, that fails on the same ambiguous triplets.




Figure 4: Cohen's κ heatmap across eleven of the twelve models (TNN omitted) on NIGHTS-100k non-tie predictions ($N = 64{,}420$). Each cell is the κ between the row and column model's binary left/right predictions on the same set of triplets. Diagonal is 1 by construction. $\kappa = 1$ is perfect agreement; $\kappa = 0$ is chance. Two blocks stand out: the DINO-LoRA block (within-block $\kappa > 0.6$), and the two DreamSim variants that agree with each other at $\kappa = 0.75$ but with LPIPS at only 0.25–0.36.

Is κ sufficient when labels have limited reproducibility? One reviewer concern is that pooled κ mixes agreement on reproducible-label triplets (X-0, ceiling 100%) with agreement on low-reproducibility triplets (2-1, ceiling 74%). If two models "agree" on a 2-1 triplet, are they agreeing on shared signal or shared noise? We address this by stratifying κ by agreement pattern: computing κ separately on the X-0 (unanimous), X-1 (strong, $X \geq 5$), and weak (2-1/3-1/4-1) subsets. Table 7 shows that the ranking of redundancy is preserved across all strata, with magnitudes declining in the expected way on weak-majority triplets where label noise is higher.

The pooled κ in Figure 4 and in the main body is therefore a weighted average over agreement patterns with different label reliability. The stratified view shows two things: first, the redundancy claim (DreamSim variants and DINO-LoRA pairs are structurally similar classifiers, LPIPS is independent) holds on the subset where labels are authoritative; second, the lower κ magnitudes on weak-majority patterns partly reflect the reduced maximum κ achievable when classifier outputs are compared against noisy labels. Both observations are consistent with the §4.3 reproducibility-ceiling analysis: on weak-majority triplets there is less reproducible signal for any classifier (or pair of classifiers) to latch onto.

Table 7: Cohen's κ stratified by human-agreement pattern on the pooled NIGHTS-100k non-tie predictions. The ranking of redundancy (DreamSim-Pretrained $\leftrightarrow$ DreamSim-Scratch highest, LPIPS $\leftrightarrow$ DreamSim lowest) is identical at every stratum. On the unanimous subset, where labels have 100% reproducibility ceiling, the DreamSim-Pretrained $\leftrightarrow$ DreamSim-Scratch agreement rises to $\kappa = 0.90$, the strongest piece of evidence that retraining the ensemble on NIGHTS-100k does not alter its decision surface.

Pair	Unanimous X-0 ($N = 20{,}005$)	Strong X-1 ($N = 7{,}922$)	Weak (2-1/3-1/4-1) ($N = 36{,}476$)	Pooled ($N = 64{,}420$)
DreamSim-Pretrained $\leftrightarrow$ DreamSim-Scratch	0.90	0.76	0.68	0.75
DreamSim-Pretrained $\leftrightarrow$ DINOv3-LoRA-Cog	0.89	0.69	0.58	0.69
DINOv2-LoRA-Cos $\leftrightarrow$ DINOv3-LoRA-Cog	0.85	0.64	0.55	0.67
DINOv3-ZS $\leftrightarrow$ DreamSim-Pretrained	0.72	0.52	0.44	0.54
LPIPS $\leftrightarrow$ DreamSim-Pretrained	0.52	0.34	0.27	0.30

D Additional experiments

This section documents experiments that did not make Table 1 but took substantial compute: alternative similarity heads on frozen DINOv3 CLS embeddings, a multi-teacher distillation backbone (C-RADIOv4), a vision-language-model-as-judge (Qwen3-VL), ClickMe attention harmonization, and qualitative traces that make the agreement-stratified story visible on individual triplets. The BAPPS ceiling is reported in the main body (§4.5).

D.0 Harmonized DINOv3 (attention alignment on ClickMe)

Fel et al. [2022] propose training a vision backbone to match human attention maps collected via ClickMe [Linsley et al., 2019]. The hypothesis is that attention-aligned features yield similarity-aligned embeddings. We tested this on DINOv3 with the authors' pretrained ClickMe attention predictor: 5-fold CV on NIGHTS-100k non-tie (matched splits to Table 1) gives Harmonized-DINOv3 $= 64.0 \pm 0.2\%$, an 8 pp drop from DINOv3 zero-shot on the same folds (Table 8). The near-zero across-fold variance indicates the drop is not noise.

The interpretation in the Discussion is the level-of-abstraction mismatch: ClickMe captures where humans look during categorization, not which compositional features drive perceived ensemble-image similarity. The result is consistent with attention-alignment being a useful signal for LPIPS-style pixel-distortion metrics but not for the mid/high-level discrimination NIGHTS requires.

Table 8: Harmonized DINOv3 on NIGHTS-100k, 5-fold CV. Zero-shot DINOv3 reproduced from Table 1 for direct comparison on the same test splits.

Model	F1	F2	F3	F4	F5	Mean $\pm$ Std	Δ
DINOv3-ZS-CLS-cos	72.4	72.3	72.1	71.4	71.7	72.0 ± 0.4	–
Harmonized DINOv3	63.8	64.1	63.9	64.4	63.9	64.0 ± 0.2	-8.0

D.1 Alternative similarity heads on frozen CLS

The main body establishes that cosine distance on DINO CLS tokens is the strongest zero-shot signal on NIGHTS-100k. A natural follow-up question is whether any other similarity function on the same frozen embedding improves that number. We swept ten alternatives spanning basic distances, kernel methods, non-Euclidean geometries, distribution-based interpretations, and learned metric-learning heads, all evaluated on the same 5-fold cross-validation on NIGHTS-100k non-tie (Table 9).

Table 9: Alternative similarity heads on frozen DINOv3 CLS embeddings, 5-fold CV on NIGHTS-100k non-tie ($N = 64{,}420$). Cosine is the baseline from Table 1. "Learned" heads are trained with pairwise BCE for 10 epochs; all other heads are parameter-free. No alternative beats plain cosine by more than 0.1 pp, within fold-to-fold s.d.; learned heads with more parameters do systematically worse. Retrieval-style losses did not help either (cosine-softmax-ranking and margin-triplet variants of cosine all remained within 0.1 pp of plain cosine on a fold-0 pilot).

Head	Type	Trainable params	Accuracy
Cosine (baseline)	parameter-free, angular	0	**72.01 $\pm$ 0.4**
Neg-dot product	parameter-free, inner	0	72.01 ± 0.3
Arc-cosine kernel (order-1)	Cho & Saul 2009	0	72.11 ± 0.3
Poincaré hyperbolic distance	non-Euclidean	0	72.09 ± 0.3
L2 Euclidean	parameter-free, metric	0	71.56 ± 0.3
L1 Manhattan	parameter-free, metric	0	71.50 ± 0.2
JSD on softmax(CLS)	distribution divergence	0	71.37 ± 0.2
Mahalanobis diag (learned)	learned metric	768	71.79 ± 0.2
Mahalanobis rank-32 (learned)	learned metric	24,576	70.26 ± 0.4
Learned bilinear rank-32	learned metric	49,152	68.35 ± 0.3
Siamese MLP on $[a, b, \lvert a-b\rvert, a \odot b]$	learned similarity	$\sim$800k	68.39 ± 0.5

Cosine, neg-dot, arc-cosine, and Poincaré differ by at most 0.1 pp, less than the fold-to-fold standard deviation. L2, L1, and JSD trail cosine by $\sim$0.5–0.7 pp. Adding parameters makes performance worse: a Mahalanobis metric with 24,576 extra parameters loses 1.7 pp, while an 800k-parameter Siamese MLP loses 3.6 pp despite access to both embeddings. The learned heads appear to fit fold-specific label noise (§4.3) rather than learn a better metric. On frozen DINO CLS embeddings, no tested head beats cosine by more than 0.1 pp, and all learned heads perform worse.

D.2 Multi-teacher distillation (negative result)

C-RADIOv4-SO400M [Conwell et al., 2024] distills DINOv3, SigLIP2, and SAM3 into a single ViT. We hypothesized that a model with stronger semantic, linguistic, and segmentation priors would produce better perceptual similarity. We applied rank-8 LoRA to qkv/proj and a cosine head on the summary token and trained for one epoch on fold 0 (approximately 28 hours at the model's required 1008×1008 input resolution for its RoPE embeddings).

Epoch-1 test accuracy on fold 0 was 58.2%, below every DINO backbone in Table 1 by 13 pp or more, and below LPIPS by 7 pp. We stopped after one epoch. The model's pretraining objectives mix spatial, semantic, and linguistic signals that appear to dilute the fine-grained synthetic-image similarity signal NIGHTS requires. Training at 224×224 is not possible without retraining the RoPE embeddings, and the full-resolution compute cost makes multi-fold cross-validation impractical for this backbone at our compute budget.

D.3 VLM-as-judge (negative result)

Modern vision-language models can describe image content at the scene level. We tested whether a VLM can directly answer the 2AFC question. Using Qwen3-VL-4B-Instruct on a 100-triplet sample from fold 0, we constructed a prompt showing the reference and two candidates with randomized A/B order, and extracted the logit ratio of the A vs. B tokens at the first generated position. We applied position randomization to remove A/B bias.

Table 10: Qwen3-VL-4B-Instruct on a 100-triplet sample of NIGHTS-100k fold 0. The stratified rows in the submitted version were incorrect and are corrected here.

Triplet subset	N	Accuracy
Unanimous (X-0)	26	69.2%
Strong-majority (X-1, $X\geq5$)	13	84.6%
Weak-majority (2-1/3-1/4-1)	61	55.7%
All	100	63.0% (Wilson 95% CI 53.2–71.8)

Qwen3-VL reaches 63.0% overall, below LPIPS and every zero-shot backbone in Table 12. On unanimous triplets it reaches 69.2%, while every zero-shot backbone exceeds 75%, and it is near chance on weak-majority triplets. Each agreement stratum has only 13 to 61 triplets, so only the overall figure should be read quantitatively. The model can reason about scene content but does poorly on the fine-grained similarity judgments NIGHTS asks for.

D.4 Model confidence versus the human vote split

The headline result is in §4.7. We map each model's score to a probability $P(\text{left})$ with out-of-fold Platt scaling (fit on four folds, applied to the fifth), define model confidence as $2|P - 0.5|$, and compare it to the confidence the human vote supports, $2|v - 0.5|$ for left-vote fraction v; the 35,580 tied triplets never enter the fit. Expected calibration error (ECE) is reported against both the binarized majority label and the human vote fraction. Figure 5 reports the full picture: confidence by agreement pattern against the confidence the votes themselves support, a reliability curve of calibrated $P(\text{left})$ against the observed vote fraction, and mean confidence on the 35,580 split-vote triplets. Figure 6 repeats the measurement cumulatively, starting from the published 20k and relaxing the agreement filter one vote pattern at a time out to the full 100k. The confidence the votes support falls from 1.000 to 0.414 across that sweep; DreamSim-Pretrained falls from 0.790 to 0.563, and the two curves cross near 70,000 triplets.

Table 11: Mean model confidence $2|P(\text{left}) - 0.5|$ by agreement pattern after out-of-fold Platt scaling, against the confidence the vote split supports. X-0 pools the 2-0 to 10-0 patterns (the one 1-0 and two 11-0 triplets are excluded).

Agreement	N	Vote-supported	DreamSim-Pretrained	DINOv1-ZS	LPIPS
50/50 (tie)	35,580	0.000	0.484	0.383	0.251
2-1	18,454	0.333	0.492	0.386	0.250
4-1	6,841	0.600	0.544	0.412	0.260
X-0	20,016	1.000	0.790	0.580	0.324




Figure 5: Model confidence against the human vote split on NIGHTS-100k. (A) confidence by agreement pattern; black is the confidence the observed vote split supports. (B) reliability against the observed vote fraction; legend gives ECE against the vote fraction and against the binarized majority label. (C) mean confidence on the 35,580 triplets where humans split 50/50. Gray bars are LoRA-trained heads reporting their native sigmoid.




Figure 6: The same measurement on the agreement split used throughout the paper. (A) the 17 raw vote patterns on the majority-vote-fraction axis of Figure 2; the unanimous block is the published 20k. (B) cumulative corpus, relaxing the filter one pattern at a time from the published 20k to the full 100k.

D.5 Per-axis stimulus manipulation results

These are the per-axis results of the Figure-6-style replica described in §4.6. We report them here, and not in the main body, because NIGHTS provides no human judgments on manipulated stimuli, and we collected none: the orientation, color, shading and blur axes therefore measure model invariance only and cannot be set against human behavior. The foreground/background axis is treated separately in the main text, where IN-9 and ObjectNet supply an external anchor.




Figure 7: DreamSim-style Figure-6 ablation replica. Accuracy drop (pp) relative to clean for each backbone $\times$ ablation. Bluer is more invariant; redder is more fragile. DINOv3 zero-shot is the most invariant overall; DreamSim-Pretrained and our own DINOv2+LoRA are among the most fragile despite the best clean accuracy. 2000 unanimous NIGHTS triplets.

1. **DINOv3 was the most invariant zero-shot backbone** on every axis except background removal. Rotation drop was ≤ 0.7 pp, grayscale drop was only 0.3 pp, mild blur actually *helped* (+1.25 pp at $\sigma = 4$), and the foreground-only drop was 1.1 pp. Its clean accuracy of 85.4% was below DINOv1's 88.5% and DreamSim-Pretrained's 93.8%, but its accuracy changed less under the tested manipulations.
2. **DreamSim-Pretrained traded invariance for clean-image accuracy.** It had the best clean score in the table (93.8%) but the worst or near-worst drop on rotation (-4.3), color (-5.7), heavy blur (-9.6), foreground (-9.05), and background (-14.5). Margin-hinge LoRA training narrows the feature geometry around the triplet distribution, which produces the best in-distribution score at the cost of cross-manipulation stability.

Both observations are statements about models. Neither supports a claim about the difference between model error and human error on these stimuli, and the revision no longer makes one.

D.6 Zero-shot backbone sweep

Every backbone below is evaluated with plain cosine on the post-norm CLS (or pooled) embedding at 224×224, with no training, on the same five folds as Table 1. The DINOv2 size sweep is repeated in Table 3.

Table 12: Zero-shot cosine accuracy on NIGHTS-100k non-tie (5-fold mean ± s.d., $N = 64{,}420$) and on the unanimous X-0 subset.

Backbone	Family	NIGHTS-100k	Unanimous X-0
LPIPS-AlexNet	CNN, supervised	65.3 ± 0.2	75.9
ResNet-152	CNN, supervised	67.1 ± 0.4	78.9
CLIP ViT-B/16	ViT, language-image	68.0 ± 0.3	80.0
ResNet-50	CNN, supervised	69.7 ± 0.3	82.4
BiT-M R101x3	CNN, supervised	70.2 ± 0.3	83.5
BagNet-33	CNN, bio-inspired	70.3 ± 0.5	83.6
ConvNeXt-Large	CNN, supervised	71.4 ± 0.3	85.4
CORnet-S	CNN, bio-inspired	71.7 ± 0.2	85.7
VOneResNet-50	CNN, bio-inspired	71.8 ± 0.6	85.7
Supervised ViT-B/16	ViT, supervised	72.4 ± 0.2	86.5
DINOv2 ViT-g/14	ViT, self-supervised	68.4 ± 0.3	80.5
DINOv2 ViT-L/14	ViT, self-supervised	69.0 ± 0.2	81.8
DINOv2 ViT-B/14	ViT, self-supervised	70.6 ± 0.4	83.9
DINOv3 ViT-B/16	ViT, self-supervised	72.0 ± 0.4	85.7
DINOv2 ViT-S/14	ViT, self-supervised	72.2 ± 0.5	85.8
DINOv1 ViT-B/16	ViT, self-supervised	74.1 ± 0.5	88.6
DreamSim ensemble, untrained	DINO+CLIP+OpenCLIP	74.5 ± 0.4	89.2

D.7 Color control for the fine-tuning gain

To test whether the 4.2 pp that training adds over the untrained DreamSim ensemble (§4.4) comes from low-level color, we computed for every one of the 64,420 non-tie triplets the χ^2 distance between the RGB histograms of each candidate and the reference, and split the triplets by whether that gap favors the human-majority candidate. The training gain was $+3.9$ pp where color could not discriminate and $+4.9$ pp where it could (95% CI ± 0.7 pp), so the gain is nearly flat across the split. A logistic regression on twelve pixel statistics alone reached 62.3%, below every zero-shot backbone in Table 12.

E Training details

This section documents the full training recipe for reproducibility. All trained models in Table 1 use the same pipeline except where explicitly noted; DreamSim-Scratch uses the authors' published training code verbatim and is documented separately at the end.

Preprocessing. Images are decoded from the NIGHTS release JPEGs, resized to 224×224 with bicubic interpolation, and center-cropped. Normalization follows the backbone: ImageNet statistics (mean $[0.485, 0.456, 0.406]$, std $[0.229, 0.224, 0.225]$) for DINOv1, DINOv2, and DINOv3; $0.5/0.5$ for C-RADIOv4; the processor-supplied normalization for DreamSim and Qwen3-VL. No data augmentation is used at training time: the triplet task is orientation-sensitive, and the reference/candidate pairing is the supervision signal.

LoRA configuration. LoRA adapters have rank 8, $\alpha = 16$, and dropout 0.05, and are inserted on the `qkv` and `proj` linear layers of every transformer block. The backbone's final LayerNorm is also unfrozen. For DINOv2 ViT-B/14 with 12 blocks this yields 442,368 LoRA parameters plus 1,536 LayerNorm parameters, which is approximately 0.5% of the 86M backbone. The DreamSim ensemble retraining uses rank 16 on the same modules to match the authors' released configuration.

Optimizer. Schedule-Free AdamW [Defazio et al., 2024] with $\beta_1 = 0.9$, $\beta_2 = 0.999$, weight decay 10^{-2}, 100 linear warm-up steps, and a constant learning rate thereafter (no cosine schedule). Separate learning rates are used: 10^{-4} for LoRA and layer-norm parameters, 2×10^{-4} for the head. Gradients are clipped to a global norm of 1.0 before each optimizer step.

Batch and compute. Batch size is 32 triplets per step (each triplet contributes three images to the forward pass). Training runs for 10 epochs over the fold's training split with batch size 32. Compute is a shared cluster of NVIDIA RTX A6000 GPUs (48 GB). A full 5-fold run of DINOv2-LoRA-Cog takes approximately 3–5 hours when five GPUs run concurrently, one per fold.

Checkpoint selection. A held-out validation split of 10% of each fold's training data selects the best-of-10-epochs checkpoint by validation accuracy; the selected checkpoint is evaluated once on the fold's test split, and that single number appears in Table 6. Per-triplet test-set predictions are persisted for every (model, fold) pair so that the Cohen's κ matrix, McNemar tests, and error-distribution analyses can be reproduced without re-running training.

DreamSim retraining from scratch. We run the authors' published training code unchanged with the released ensemble configuration: DINO+CLIP+OpenCLIP, rank-16 LoRA, margin-0.05 hinge loss, batch size 16, 6 epochs. The release filters training triplets to those with at least 6 votes, so the scratch model sees only strong-majority triplets during training; we evaluate on the same full non-tie test fold as every other model in Table 1. This mismatch is the point of the comparison, not an oversight: it isolates what the authors' training recipe would produce when the 100k distribution is available.

F Shape-only class separability and retrieval

Table 13: Shape-only class separability. Leave-one-out nearest-prototype accuracy on the Geirhos filled-silhouette and edge stimuli. Chance is 6.25% (16 classes). Referenced from §4.6.

Backbone	Silh 1-NN	Silh proto	Edges 1-NN	Edges proto
ResNet-50	77.5	81.3	63.1	67.5
DINOv1	71.3	78.1	66.3	68.1
CLIP-ViT-B/16	73.1	78.8	79.4	81.3
DINOv2	81.3	86.3	71.3	80.0
DINOv3	82.5	87.5	86.9	91.3
ConvNeXt-Large	84.4	87.5	90.0	93.8




Figure 8: Shape-only nearest-neighbor retrieval. For four query silhouettes (bicycle, cat, elephant, keyboard), each backbone's top-3 nearest silhouettes by cosine distance in CLS space. Green outline: match; red: mismatch. Every backbone, including ResNet-50 with its near-zero cue-conflict shape-bias, retrieves predominantly within-class; shape representation is present in every backbone we tested.

Tie-based bias audit. On the 7,116-triplet tie subset held out per fold, LoRA-trained models predict left with frequency 49.5–51.1% (no positional bias). Zero-shot DINOs show 49.6–50.8% and DreamSim 51%, also near chance. The one model with tie bias outside that range is Qwen3-VL-4B (55% left, confidence 0.30), consistent with known VLM positional preferences. LoRA adaptation on NIGHTS-100k does not induce spurious tie preferences.




Figure 9: The cost of clean-image accuracy. Each point is a backbone; vertical axis is the mean magnitude of accuracy drop across the 11 Fig-6 ablation conditions. Zero-shot backbones (circles) cluster in the low-fragility region; LoRA-trained models and DreamSim-Pretrained (diamonds) shift up and right. Dashed line is a least-squares trend.

G Full 2AFC-vs-JND axis table

Table 14: Per-backbone 2AFC accuracy (Fig-6 clean, 2000 unanimous triplets) and JND AUC (1,216 reference–candidate pairs from 608 triplets, same/different). Extended form of Figure 17. Among the zero-shot backbones the two rankings are only weakly related (Spearman $\rho = 0.37$, $p = 0.19$); the two models trained on NIGHTS 2AFC lead on both. A single AUC carries a 95% bootstrap interval of about ± 0.04.

Backbone	2AFC acc (%)	JND AUC	Family
DINOv1	88.45	0.674	DINO self-distill
DINOv2	84.65	0.677	DINO self-distill
DINOv3	85.35	0.697	DINO self-distill
CLIP-ViT-B/16	80.60	0.661	image-text
OpenCLIP-ViT-B/16	83.95	0.696	image-text
ViT-B/16	86.90	0.670	label-supervised ViT
ConvNeXt-Large	85.40	0.648	modern CNN
ResNet-50	84.05	0.647	classical CNN
ResNet-152	83.45	0.653	classical CNN
BiT-M R101x3	83.50	0.634	JFT-scale CNN
CORnet-S	86.60	0.675	biologically-inspired
BagNet-33	84.20	0.651	biologically-inspired
VOneResNet50	85.55	0.674	biologically-inspired
DreamSim-ZS	89.00	0.676	concatenated ensemble, ZS
DINOv2 + LoRA	89.30	0.720	LoRA-trained on NIGHTS
DreamSim-Pretrained	93.75	0.727	LoRA-trained ensemble

H BAPPS-vs-NIGHTS quadrant view




Figure 10: Quadrant view of Figure 11. Dashed lines mark the 69.0% (BAPPS) and 70.1% (NIGHTS) reference levels of Table 4. The top-right quadrant lies above both. Two models fall inside it: DreamSim-Pretrained, after supervised training on the NIGHTS-20k subset, and zero-shot DINOv1, with no training.




Figure 11: Perceptual similarity is a spectrum. Each model's accuracy at low-level BAPPS (left) connects to its accuracy at mid-to-high-level NIGHTS-100k (right). Crossing lines show rank inversion across the spectrum: LPIPS is a BAPPS specialist that trails on NIGHTS; DINOv2/v3 invert the pattern. Two models score above both reference levels: DreamSim after supervised NIGHTS-20k training, and zero-shot DINOv1 with no training.

Table 15: Split-half agreement for BAPPS 2AFC validation (5 votes per triplet): the probability that the two halves of a triplet's votes choose the same majority, a conservative companion to the fresh-panel repeatability of §4.3 (68.3% for 3-2, 94.2% for 4-1). The lower rows give per-category 2AFC accuracy against the binary majority label; their unweighted mean is the BAPPS column of Table 4.

Category	CNN	Traditional	Super-res	Color	Frame-int	Deblur
N	4,720	4,720	10,856	4,720	1,888	9,440
Ceiling	83.2%	79.1%	70.0%	64.1%	62.8%	59.6%
LPIPS-AlexNet	86.7	77.7	76.2	66.3	66.9	63.8
DINOv1-ZS	85.2	80.0	73.2	62.0	66.1	62.4
DINOv2-ZS	81.0	75.4	63.7	58.1	66.6	59.1
DINOv3-ZS	83.2	77.2	65.8	59.8	64.4	60.2
DreamSim-Pretrained	86.8	82.0	75.0	67.7	67.5	62.6

All BAPPS: N=36,344, split-half agreement = 69.0%.

Table 16: Accuracy on ImageNet-prompted and non-ImageNet-prompted subsets of NIGHTS-100k non-tie. Δ is ImageNet minus non-ImageNet.

Model	ImageNet	Non-ImageNet	Δ
LPIPS-AlexNet-Pretrained	64.6	66.1	-1.5
DINOv1-ZS-CLS-cos	74.5	73.6	$+0.9$
DINOv3-ZS-CLS-cos	73.0	70.7	$+2.3$
DINOv2-LoRA-Cos	78.7	77.9	$+0.7$
DINOv3-LoRA-Cog	79.4	77.9	$+1.5$
DreamSim-Pretrained	81.0	80.3	$+0.8$
DreamSim-Scratch	79.0	78.3	$+0.7$




Figure 12: Left: share of each model's NIGHTS-100k errors, stratified by the human-agreement pattern of the underlying triplet (weak 2-1/3-1/4-1, strong X-1 with $X \geq 5$, unanimous X-0). Right: fraction of each model's wrong predictions where at least one human voter agreed with the model. The best models are almost never alone against the humans (DreamSim 96.6%, DINOv3-LoRA 92.0%); their errors live where humans themselves were split.

I Extended §4.6 figures: shape bias, hGRU collapse, LoRA trajectory, 2AFC vs. JND

These five figures were referenced from §4.6 but deferred here for length.




Figure 13: Cue-conflict shape bias on the Geirhos 2018 stimuli. DINOv1 preferences are texture-dominated (10.3%); DINOv2 (23.2%) and DINOv3 (37.3%) are more than three times more shape-biased. ResNet-50 is the most texture-dominant (3.75%); ConvNeXt-Large (19.75%) and CLIP-ViT-B/16 (29.83%) sit between. Zero-shot, 1200 cue-conflict images, 16 classes. Humans score $\sim$95% on the same stimuli [Geirhos et al., 2019].




Figure 14: Radial-mask sensitivity sweep. Accuracy on 2000 unanimous triplets as a function of radial mask radius, keeping only the center disc (fg, left) or only the surround ring (bg, right). DINO backbones transition smoothly; ResNet-50+hGRU collapses to chance on any foreground radius in $[0.1, 0.5]$ and any background radius below 0.7, revealing that the lateral-recurrence stage learns a globally coupled representation that fails under any spatial mask.



Figure 15: Three high-vote NIGHTS unanimous triplets where DINOv2 + LoRA flips the majority-choice decision. Green border = human-majority candidate; red border = LoRA's (wrong) choice. Each panel is overlaid with last-layer CLS attention and annotated with the $\cos(\mathrm{ref}, \cdot)$ values the models computed. The examples share two signatures. (i) LoRA's flips occur at cos margins as small as 0.005 (spoonbill: 0.905 vs 0.910), exactly the voter-noise-scale differences the reproducibility analysis of Section 4.3 warned about; (ii) attention geometry is nearly identical between ZS and LoRA, so the shortcut is encoded in the feature representation (sim(full, fg-only) drops consistently for LoRA) and not in where the model looks. Pairwise similarities computed with DINOv2 + rank-8 LoRA + cosine at 224×224.




Figure 16: Controlled LoRA-strength sweep on a single backbone. DINOv2 + rank-8 LoRA trained for 0–8 epochs on NIGHTS-20k unanimous, each checkpoint evaluated on the 2000-triplet Fig-6 ablation suite. Gray dots: 16-backbone context from Figure 9. Phase 1 (epoch $0 \rightarrow 1$) mirrors the cross-backbone invariance tax slope. Phase 2 (epochs 1–8) keeps climbing the fragility axis while clean accuracy reverts toward the zero-shot baseline. Within-backbone evidence that the invariance tax is causal, not a family-level confound.




Figure 17: 2AFC accuracy and JND AUC per backbone. Horizontal axis: NIGHTS 2AFC accuracy on the 2000 unanimous-triplet subset; vertical axis: JND AUC on the 1,216 reference–candidate pairs of the 608 JND triplets. The green arrows trace DINOv1 $\rightarrow$ v2 $\rightarrow$ v3: v1 leads on 2AFC by 3.1–3.8 pp, but the three lie within 0.03 AUC of each other on JND, inside the ± 0.04 sampling interval. The two models trained on NIGHTS 2AFC (upper right) lead on both tasks.

J Qualitative triplet traces

The analyses in the main body are aggregate. This section shows the individual stimuli behind them, drawn unmodified from the released corpus. Figure 18 illustrates what the agreement patterns of §4.3 look like on single triplets, one per pattern from 2-1 to 7-0. A 2-1 triplet carries a label a fresh panel of three annotators would reproduce a third of the time; a 7-0 triplet carries one that reproduces every time. Both contribute equally to a headline accuracy.

Figure 19 shows the complementary case: triplets with 8 to 10 votes on one side, where the label is as stable as NIGHTS labels get, and where DreamSim-Pretrained still selects the other candidate. These are the errors the reproducibility ceiling does not explain, and they are 3.4% of that model's disagreements with the majority label.

Figure 20 shows stimuli carrying both NIGHTS labels. All 608 shared triplets come from the X-0 unanimous tier, so the 2AFC/JND comparison of §5 is a comparison on the easy subset and not the hard one. Even so, the labels conflict on 44% of the 1,216 reference–candidate pairs, almost always because JND voters judged the unanimous 2AFC winner different from the reference (82% of winners). A stricter, relative test asks whether JND voters at least judged the winner less different than the loser: they did on 42.3% of triplets, could not separate the two on 39.6%, and judged the winner more different on 18.1%.




Figure 18: One NIGHTS-2AFC triplet per vote pattern. Reference, the candidate the human majority chose, and the alternative, with the vote split annotators produced. Prompts and triplet ids are given beside each row.




Figure 19: Unanimous triplets that the strongest model in Table 1 gets wrong. Vote pattern and prompt are given under each panel.




Figure 20: Triplets whose two human labels conflict. (a, b) Unanimous 10/10 2AFC winners that all three JND voters judged different from the reference, as were the losers: the typical conflict, a forced choice between two visibly different images. (c) A unanimous 2AFC loser that all three JND voters judged the same as the reference. (d) A relative contradiction: JND voters judged the 2AFC winner more different from the reference than the loser. Vote counts are given above each image.

K Where human voters disagree: splits within and conflicts across the two NIGHTS tasks

NIGHTS carries two kinds of human disagreement, and a majority label shows neither. The first is within a task: voters split on the same item. The second is across tasks: the 2AFC label and the JND label of the same image pair point in opposite directions. This section reports both from the released votes.

Splits within 2AFC. Of the 64,420 non-tie triplets, 36,476 (57%) are weak majorities (2-1, 3-1 or 4-1) and 7,922 have a single dissent among five or more voters; a further 35,580 triplets are ties. Because voting stopped at the first dissent, a split triplet usually has only three or four voters, and a fresh panel of the same size reproduces a 2-1 majority only 74% of the time (§4.3). The DreamSim paper reports the split only indirectly, as the roughly 20% of triplets that survived its unanimity filter, and the public release contains only the unanimous triplets.

Splits within JND. JND voters judged each reference–candidate pair "same" or "different": three voters for 1,184 of the 1,216 pairs and six for the other 32. Of the pairs, 643 (52.9%) were unanimous and 573 (47.1%) were split; none was tied. Applying the fresh-panel resampling of §4.3 to the JND votes, a split JND label is reproduced 74.7% of the time and the average JND label 88.1%, the same reliability profile as 2AFC. The DreamSim paper takes the majority of the three votes as the label and reports no split rate. It describes keeping triplets in which humans found exactly one candidate identical; in the release that is 137 of the 608 triplets (23%).

Conflicts across the two tasks. Table 17 cross-tabulates the two labels on the 1,216 pairs. A pair is consistent when the 2AFC winner is judged "same" or the loser "different," and in conflict when the winner is judged "different" or the loser "same." The conflicts sit almost entirely in one place: unanimous 2AFC winners that JND voters judged different from the reference. This holds whether the JND vote was split (249 winners) or unanimous (251 winners), so it is not produced by noise in three-vote JND labels. At the triplet level, JND voters judged neither candidate "same" in 466 of the 608 triplets (77%): the unanimous 2AFC vote chose between two images that JND voters saw as different from the reference. Of the 137 triplets in which exactly one candidate was judged "same," that candidate was the 2AFC loser in 34 (25%). The share of winners judged different does not fall as 2AFC agreement rises: 81% at 6-0 and 7-0, 82% at 8-0, 84% at 9-0, and 91% at 10-0 (22 triplets). Figure 20 shows examples.

Table 17: The two human labels on the 1,216 reference–candidate pairs of the 608 NIGHTS-JND triplets, all unanimous in 2AFC. Columns give the JND vote, unanimous or split, grouped by its majority. Bold cells point against the 2AFC choice (chosen judged "different," rejected judged "same"); every candidate is a visibly distorted image, so the first kind is expected, and the informative comparison is between the two rows. The last column is each row's share pointing against the 2AFC choice.

	JND majority "different"		JND majority "same"		
2AFC label	unanimous	split	split	unanimous	against 2AFC
Winner (chosen), $n = 608$	**251**	**249**	92	16	82.2%
Loser (rejected), $n = 608$	372	197	**35**	**4**	6.4%
All pairs, $n = 1{,}216$	623	446	127	20	44.3%

What the conflict means. 2AFC is a forced comparison with no "neither" option: a candidate wins by being closer to the reference than the alternative, however different both are. JND asks whether a single candidate can be told apart from the reference. A unanimous 2AFC label therefore certifies a ranking, not similarity, and the 77% of triplets with both candidates judged different show that most of these unanimous labels rank two visibly different images. Scoring a model against the majority label of either task discards both the splits within each task and the conflict between them.

NeurIPS Paper Checklist

1. **Claims**

   Question: Do the main claims made in the abstract and introduction accurately reflect the paper's contributions and scope?

   Answer: [Yes]

   Justification: The abstract and introduction state the thesis (cosine on a self-supervised backbone captures most of the reproducible perceptual signal NIGHTS measures) and the supporting evidence: a closed-form reproducibility ceiling, foreground-only fragility under fine-tuning, and 2AFC–JND label dissociation. All numerical claims appear in the body and are reproduced from the released per-fold predictions.

   Guidelines:

   - The answer [N/A] means that the abstract and introduction do not include the claims made in the paper.
   - The abstract and/or introduction should clearly state the claims made, including the contributions made in the paper and important assumptions and limitations. A [No] or [N/A] answer to this question will not be perceived well by the reviewers.
   - The claims made should match theoretical and experimental results, and reflect how much the results can be expected to generalize to other settings.
   - It is fine to include aspirational goals as motivation as long as it is clear that these goals are not attained by the paper.

2. **Limitations**

   Question: Does the paper discuss the limitations of the work performed by the authors?

   Answer: [Yes]

   Justification: Section 6 lists seven explicit caveats: NIGHTS-specific method comparisons, the scope of backbone coverage, fixed LoRA rank, the ambiguous-pair vs minority-bias interpretation of the agreement statistic, the qualitative scale of the JND audit, the within-population scope of the reproducibility ceiling, and the absence of per-rater data and demographics.

   Guidelines:

   - The answer [N/A] means that the paper has no limitation while the answer [No] means that the paper has limitations, but those are not discussed in the paper.
   - The authors are encouraged to create a separate "Limitations" section in their paper.
   - The paper should point out any strong assumptions and how robust the results are to violations of these assumptions (e.g., independence assumptions, noiseless settings, model well-specification, asymptotic approximations only holding locally). The authors should reflect on how these assumptions might be violated in practice and what the implications would be.
   - The authors should reflect on the scope of the claims made, e.g., if the approach was only tested on a few datasets or with a few runs. In general, empirical results often depend on implicit assumptions, which should be articulated.
   - The authors should reflect on the factors that influence the performance of the approach. For example, a facial recognition algorithm may perform poorly when image resolution is low or images are taken in low lighting. Or a speech-to-text system might not be used reliably to provide closed captions for online lectures because it fails to handle technical jargon.
   - The authors should discuss the computational efficiency of the proposed algorithms and how they scale with dataset size.
   - If applicable, the authors should discuss possible limitations of their approach to address problems of privacy and fairness.
   - While the authors might fear that complete honesty about limitations might be used by reviewers as grounds for rejection, a worse outcome might be that reviewers discover limitations that aren't acknowledged in the paper. The authors should use their best

judgment and recognize that individual actions in favor of transparency play an important role in developing norms that preserve the integrity of the community. Reviewers will be specifically instructed to not penalize honesty concerning limitations.

3. **Theory assumptions and proofs**

   Question: For each theoretical result, does the paper provide the full set of assumptions and a complete (and correct) proof?

   Answer: [N/A]

   Justification: The paper makes empirical claims about benchmark behaviour. The reproducibility ceiling in Section 4.3 is computed in closed form by resampling each triplet's votes; no formal theorems are stated.

   Guidelines:

   - The answer [N/A] means that the paper does not include theoretical results.
   - All the theorems, formulas, and proofs in the paper should be numbered and cross-referenced.
   - All assumptions should be clearly stated or referenced in the statement of any theorems.
   - The proofs can either appear in the main paper or the supplemental material, but if they appear in the supplemental material, the authors are encouraged to provide a short proof sketch to provide intuition.
   - Inversely, any informal proof provided in the core of the paper should be complemented by formal proofs provided in appendix or supplemental material.
   - Theorems and Lemmas that the proof relies upon should be properly referenced.

4. **Experimental result reproducibility**

   Question: Does the paper fully disclose all the information needed to reproduce the main experimental results of the paper to the extent that it affects the main claims and/or conclusions of the paper (regardless of whether the code and data are provided or not)?

   Answer: [Yes]

   Justification: All twelve methods use the same fold definitions (KFold, seed 42, sorted by triplet id); training hyperparameters appear in Section 3.3 and Appendix E; per-triplet test predictions for every method and fold are in the released code package.

   Guidelines:

   - The answer [N/A] means that the paper does not include experiments.
   - If the paper includes experiments, a [No] answer to this question will not be perceived well by the reviewers: Making the paper reproducible is important, regardless of whether the code and data are provided or not.
   - If the contribution is a dataset and/or model, the authors should describe the steps taken to make their results reproducible or verifiable.
   - Depending on the contribution, reproducibility can be accomplished in various ways. For example, if the contribution is a novel architecture, describing the architecture fully might suffice, or if the contribution is a specific model and empirical evaluation, it may be necessary to either make it possible for others to replicate the model with the same dataset, or provide access to the model. In general. releasing code and data is often one good way to accomplish this, but reproducibility can also be provided via detailed instructions for how to replicate the results, access to a hosted model (e.g., in the case of a large language model), releasing of a model checkpoint, or other means that are appropriate to the research performed.
   - While NeurIPS does not require releasing code, the conference does require all submissions to provide some reasonable avenue for reproducibility, which may depend on the nature of the contribution. For example
     (a) If the contribution is primarily a new algorithm, the paper should make it clear how to reproduce that algorithm.
     (b) If the contribution is primarily a new model architecture, the paper should describe the architecture clearly and fully.

(c) If the contribution is a new model (e.g., a large language model), then there should either be a way to access this model for reproducing the results or a way to reproduce the model (e.g., with an open-source dataset or instructions for how to construct the dataset).

(d) We recognize that reproducibility may be tricky in some cases, in which case authors are welcome to describe the particular way they provide for reproducibility. In the case of closed-source models, it may be that access to the model is limited in some way (e.g., to registered users), but it should be possible for other researchers to have some path to reproducing or verifying the results.

5. **Open access to data and code**

   Question: Does the paper provide open access to the data and code, with sufficient instructions to faithfully reproduce the main experimental results, as described in supplemental material?

   Answer: [Yes]

   Justification: The released code package contains the analysis pipeline, fold definitions, per-triplet predictions for all twelve methods, retrained checkpoints, and the standalone reproducibility-ceiling script. NIGHTS and BAPPS are pre-existing public datasets and are not redistributed; their original sources are cited.

   Guidelines:

   - The answer [N/A] means that paper does not include experiments requiring code.
   - Please see the NeurIPS code and data submission guidelines (`https://neurips.cc/public/guides/CodeSubmissionPolicy`) for more details.
   - While we encourage the release of code and data, we understand that this might not be possible, so [No] is an acceptable answer. Papers cannot be rejected simply for not including code, unless this is central to the contribution (e.g., for a new open-source benchmark).
   - The instructions should contain the exact command and environment needed to run to reproduce the results. See the NeurIPS code and data submission guidelines (`https://neurips.cc/public/guides/CodeSubmissionPolicy`) for more details.
   - The authors should provide instructions on data access and preparation, including how to access the raw data, preprocessed data, intermediate data, and generated data, etc.
   - The authors should provide scripts to reproduce all experimental results for the new proposed method and baselines. If only a subset of experiments are reproducible, they should state which ones are omitted from the script and why.
   - At submission time, to preserve anonymity, the authors should release anonymized versions (if applicable).
   - Providing as much information as possible in supplemental material (appended to the paper) is recommended, but including URLs to data and code is permitted.

6. **Experimental setting/details**

   Question: Does the paper specify all the training and test details (e.g., data splits, hyperparameters, how they were chosen, type of optimizer) necessary to understand the results?

   Answer: [Yes]

   Justification: Methods, hyperparameters, and dataset processing are documented in Section 3 (Method) and Appendix E (Training details). DreamSim-Scratch uses the authors' published training code unchanged, also documented in Appendix E.

   Guidelines:

   - The answer [N/A] means that the paper does not include experiments.
   - The experimental setting should be presented in the core of the paper to a level of detail that is necessary to appreciate the results and make sense of them.
   - The full details can be provided either with the code, in appendix, or as supplemental material.

7. **Experiment statistical significance**

Question: Does the paper report error bars suitably and correctly defined or other appropriate information about the statistical significance of the experiments?

Answer: [Yes]

Justification: Table 1 reports 5-fold mean and standard deviation. We do not report pairwise significance tests: gaps inside the label-noise band quantified in §4.3 are not separable from label noise regardless of significance.

Guidelines:

- The answer [N/A] means that the paper does not include experiments.
- The authors should answer [Yes] if the results are accompanied by error bars, confidence intervals, or statistical significance tests, at least for the experiments that support the main claims of the paper.
- The factors of variability that the error bars are capturing should be clearly stated (for example, train/test split, initialization, random drawing of some parameter, or overall run with given experimental conditions).
- The method for calculating the error bars should be explained (closed form formula, call to a library function, bootstrap, etc.)
- The assumptions made should be given (e.g., Normally distributed errors).
- It should be clear whether the error bar is the standard deviation or the standard error of the mean.
- It is OK to report 1-sigma error bars, but one should state it. The authors should preferably report a 2-sigma error bar than state that they have a 96% CI, if the hypothesis of Normality of errors is not verified.
- For asymmetric distributions, the authors should be careful not to show in tables or figures symmetric error bars that would yield results that are out of range (e.g., negative error rates).
- If error bars are reported in tables or plots, the authors should explain in the text how they were calculated and reference the corresponding figures or tables in the text.

8. **Experiments compute resources**

Question: For each experiment, does the paper provide sufficient information on the computer resources (type of compute workers, memory, time of execution) needed to reproduce the experiments?

Answer: [Yes]

Justification: Each LoRA training run completes in roughly 8 GPU-hours on a single A6000. The full 5-fold cross-validation across all twelve methods uses approximately 400 A6000-hours; zero-shot evaluation is approximately 30 GPU-minutes per backbone.

Guidelines:

- The answer [N/A] means that the paper does not include experiments.
- The paper should indicate the type of compute workers CPU or GPU, internal cluster, or cloud provider, including relevant memory and storage.
- The paper should provide the amount of compute required for each of the individual experimental runs as well as estimate the total compute.
- The paper should disclose whether the full research project required more compute than the experiments reported in the paper (e.g., preliminary or failed experiments that didn't make it into the paper).

9. **Code of ethics**

Question: Does the research conducted in the paper conform, in every respect, with the NeurIPS Code of Ethics `https://neurips.cc/public/EthicsGuidelines`?

Answer: [Yes]

Justification: The paper conforms to the NeurIPS Code of Ethics. Limitations and broader impact are explicitly discussed in Section 6 and the Broader Impact section.

Guidelines:

- The answer [N/A] means that the authors have not reviewed the NeurIPS Code of Ethics.
- If the authors answer [No], they should explain the special circumstances that require a deviation from the Code of Ethics.
- The authors should make sure to preserve anonymity (e.g., if there is a special consideration due to laws or regulations in their jurisdiction).

10. **Broader impacts**

    Question: Does the paper discuss both potential positive societal impacts and negative societal impacts of the work performed?

    Answer: [Yes]

    Justification: Discussed in the Broader Impact and Reproducibility section. The principal effect is improved research hygiene around a widely used benchmark; we identify no direct negative societal impact.

    Guidelines:

    - The answer [N/A] means that there is no societal impact of the work performed.
    - If the authors answer [N/A] or [No], they should explain why their work has no societal impact or why the paper does not address societal impact.
    - Examples of negative societal impacts include potential malicious or unintended uses (e.g., disinformation, generating fake profiles, surveillance), fairness considerations (e.g., deployment of technologies that could make decisions that unfairly impact specific groups), privacy considerations, and security considerations.
    - The conference expects that many papers will be foundational research and not tied to particular applications, let alone deployments. However, if there is a direct path to any negative applications, the authors should point it out. For example, it is legitimate to point out that an improvement in the quality of generative models could be used to generate Deepfakes for disinformation. On the other hand, it is not needed to point out that a generic algorithm for optimizing neural networks could enable people to train models that generate Deepfakes faster.
    - The authors should consider possible harms that could arise when the technology is being used as intended and functioning correctly, harms that could arise when the technology is being used as intended but gives incorrect results, and harms following from (intentional or unintentional) misuse of the technology.
    - If there are negative societal impacts, the authors could also discuss possible mitigation strategies (e.g., gated release of models, providing defenses in addition to attacks, mechanisms for monitoring misuse, mechanisms to monitor how a system learns from feedback over time, improving the efficiency and accessibility of ML).

11. **Safeguards**

    Question: Does the paper describe safeguards that have been put in place for responsible release of data or models that have a high risk for misuse (e.g., pre-trained language models, image generators, or scraped datasets)?

    Answer: [N/A]

    Justification: We release analysis code, vote-count statistics, and similarity-metric checkpoints with no high-risk capabilities (no generative model weights, no demographic-classification models, no surveillance-relevant artefacts).

    Guidelines:

    - The answer [N/A] means that the paper poses no such risks.
    - Released models that have a high risk for misuse or dual-use should be released with necessary safeguards to allow for controlled use of the model, for example by requiring that users adhere to usage guidelines or restrictions to access the model or implementing safety filters.
    - Datasets that have been scraped from the Internet could pose safety risks. The authors should describe how they avoided releasing unsafe images.

- We recognize that providing effective safeguards is challenging, and many papers do not require this, but we encourage authors to take this into account and make a best faith effort.

12. **Licenses for existing assets**

    Question: Are the creators or original owners of assets (e.g., code, data, models), used in the paper, properly credited and are the license and terms of use explicitly mentioned and properly respected?

    Answer: [Yes]

    Justification: NIGHTS [Fu et al., 2023] and BAPPS [Zhang et al., 2018] are used under their published research-use terms. DINOv1/v2/v3 backbones are used under their respective public releases. All assets are credited in the bibliography.

    Guidelines:

    - The answer [N/A] means that the paper does not use existing assets.
    - The authors should cite the original paper that produced the code package or dataset.
    - The authors should state which version of the asset is used and, if possible, include a URL.
    - The name of the license (e.g., CC-BY 4.0) should be included for each asset.
    - For scraped data from a particular source (e.g., website), the copyright and terms of service of that source should be provided.
    - If assets are released, the license, copyright information, and terms of use in the package should be provided. For popular datasets, `paperswithcode.com/datasets` has curated licenses for some datasets. Their licensing guide can help determine the license of a dataset.
    - For existing datasets that are re-packaged, both the original license and the license of the derived asset (if it has changed) should be provided.
    - If this information is not available online, the authors are encouraged to reach out to the asset's creators.

13. **New assets**

    Question: Are new assets introduced in the paper well documented and is the documentation provided alongside the assets?

    Answer: [Yes]

    Justification: The released code package includes a README, requirements.txt, MIT LICENSE, and per-method documentation. Fold definitions and per-triplet predictions are documented inline in the analysis package.

    Guidelines:

    - The answer [N/A] means that the paper does not release new assets.
    - Researchers should communicate the details of the dataset/code/model as part of their submissions via structured templates. This includes details about training, license, limitations, etc.
    - The paper should discuss whether and how consent was obtained from people whose asset is used.
    - At submission time, remember to anonymize your assets (if applicable). You can either create an anonymized URL or include an anonymized zip file.

14. **Crowdsourcing and research with human subjects**

    Question: For crowdsourcing experiments and research with human subjects, does the paper include the full text of instructions given to participants and screenshots, if applicable, as well as details about compensation (if any)?

    Answer: [N/A]

    Justification: We do not run new human-subjects studies. All similarity labels are re-used from the public NIGHTS and BAPPS releases.

    Guidelines:

- The answer [N/A] means that the paper does not involve crowdsourcing nor research with human subjects.
- Including this information in the supplemental material is fine, but if the main contribution of the paper involves human subjects, then as much detail as possible should be included in the main paper.
- According to the NeurIPS Code of Ethics, workers involved in data collection, curation, or other labor should be paid at least the minimum wage in the country of the data collector.

15. **Institutional review board (IRB) approvals or equivalent for research with human subjects**

    Question: Does the paper describe potential risks incurred by study participants, whether such risks were disclosed to the subjects, and whether Institutional Review Board (IRB) approvals (or an equivalent approval/review based on the requirements of your country or institution) were obtained?

    Answer: [N/A]

    Justification: No new human-subjects research was conducted. We re-analyse pre-existing public annotation data.

    Guidelines:

    - The answer [N/A] means that the paper does not involve crowdsourcing nor research with human subjects.
    - Depending on the country in which research is conducted, IRB approval (or equivalent) may be required for any human subjects research. If you obtained IRB approval, you should clearly state this in the paper.
    - We recognize that the procedures for this may vary significantly between institutions and locations, and we expect authors to adhere to the NeurIPS Code of Ethics and the guidelines for their institution.
    - For initial submissions, do not include any information that would break anonymity (if applicable), such as the institution conducting the review.

16. **Declaration of LLM usage**

    Question: Does the paper describe the usage of LLMs if it is an important, original, or non-standard component of the core methods in this research? Note that if the LLM is used only for writing, editing, or formatting purposes and does *not* impact the core methodology, scientific rigor, or originality of the research, declaration is not required.

    Answer: [Yes]

    Justification: A large language model was used as a writing assistant on parts of the manuscript and as a coding assistant during analysis script development. The LLM did not contribute to research ideation, experiment design, or data interpretation; all empirical results come from the released code and predictions and are independently reproducible.

    Guidelines:

    - The answer [N/A] means that the core method development in this research does not involve LLMs as any important, original, or non-standard components.
    - Please refer to our LLM policy in the NeurIPS handbook for what should or should not be described.